

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-20714-00-00  
Spot: SENENW Sec/Twnshp/Rge: 27-10S-18W  
4290 feet from S Section Line, 2970 feet from E Section Line  
Lease/Unit Name: EILERS WEST Well Number: 1  
County: ROOKS Total Vertical Depth: 3639 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N. MARKET, STE 710  
WICHITA, KS 67202

Production Casing Size: 4.5 feet: 3635 150 SX CMT  
Surface Casing Size: 8.625 feet: 221 150 SX CMT

118.27

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/07/2003 1:00 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: GARY LENDENMUTH Company: AMERICAN ENERGIES CORPORAT Phone: (316) 263-5785

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.  
PBTD 3600'. Packer stuck at 1460'. Rods parted at 1306'.  
Production perfs 3212' - 3456'.  
Fluid level 250' from surface.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 10/07/2003 3:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Swift Services pumped 5 sxs 60/40 pozmix - 10% gel down backside. S.I.P. 600#.  
Hooked to 2 3/8" tubing and pumped 75 sxs cement down tubing cwc. (1770').  
Backed tubing off at 1020'. Laid down.  
Tied onto 4 1/2" casing - pumped 170 sxs neat cement.  
Max. P.S.I. 800#. S.I.P. 600#.

RECEIVED  
10-9-03  
OCT 09 2003  
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

*Richard Williams*

(TECHNICIAN)

INVOICED

DATE 10-9-03

INV. NO. 2004060591

Form CP-2/3

OCT 08 2003

E.A. BERRY  
 BOX 385  
 NEWTON, KS.  
 CONTR. HELBERG

FILERS-WEST  
 CITY: ROOKS  
 FIELD: FILERS

27-10-15W  
 SE NE 1/4

GEOL. LAMOND GRAY

NO. 2058 GL. CH. 9/14/77. CARD ISSUED 10/13/77. P 23 BOPD, NW  
 ARB OH 5635-39

+	+	+
+	+	+

API: 15-163-20.714

LOG	TOPS	DEPTH	DATUM
SC	1407	+ 651	
TOP	3032	- 974	
HEEP	3250	-1192	
TOP	3266	-1208	
LANS	3290	-1232	
BKC	3525	-1467	
SEMI CONC.	3554	-1476	
ARE	3635	-1575	
RTD	3639	-1581	

8-5/8" 221; 4 1/2" 3635/150sx  
 DST (1) 3410-3524/30-45-30-45, 100' o  
 SPKD M, SIP 594-517#, FP 103-129#  
 MICT - CO, (ARB OH) AC 250, POP, P  
 23 BOPD, GR 21°

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS