

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22287-00-00
Spot: E2NESE Sec/Twnshp/Rge: 30-10S-18W
530 feet from N Section Line, 330 feet from E Section Line
Lease/Unit Name: DAUWE B Well Number: 1
County: ROOKS Total Vertical Depth: 3680 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

Conductor Pipe: Size feet: 119.60
Surface Casing: Size 8.625 feet: 216 135 SX CMT
Production: Size 5.5 feet: 3676 150 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/26/2002 11:00 AM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: LAWRENCE W. JACKSON Company: AMERICAN ENERGIES CORPORAT Phone: (785) 483-2627

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 10% gel - 700# hulls.
D.V. at 1433' - 200 sxs cement.
Perfs at 3344'-3349'; 3393'-3397'; 3238'-3242'; 3214'-3218'.

Plugging Proposal Received By: PAT STAAB WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/26/2002 12:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Allied Cementing Company tied onto backside and pumped 5 sxs 60/40 pozmix.
Max. P.S.I. 600#. S.I.P. 500#.
Tied onto 5 1/2" casing and pumped 320 sxs 60/40 pozmix with 700# hulls mixed in.
Max. P.S.I. 1200#. S.I.P. 1000#.


RECEIVED
1-3-03
JAN 03 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY - TICKET #11333.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

INVOICED

DATE 1-3-03

INV. NO. 2003061027

Form CP-2/3

DEC 30 2002

REPLACEMENT CARD

KENNY BROWN ENTERPRISES /
KENNETH O. BROWN
DRAWER 340

30-10-18W
530'FNL &
330'FEL, SE/4

PLAINVILLE, KS 67663


#1 "B" DAUWE

CONTR DREILING OIL, INC.

CTY ROOKS

GEOLOGICAL

FIELD ORDWAY WEST EXT
(1/8 S)



ELV 2068 KB SPD 2/12/84 CARD ISSUED 4/12/84 IP P 4.2 BO & 76 BWPD
2063 GL LKC 3288-3430 OA

| LOG | Tops | Depth | Datum |
|--------|--------|-------|-------|
| ANH | 1422 + | 646 | |
| B/ ANH | 1459 + | 609 | |
| TOP | 3047 - | 979 | |
| HEEB | 3267 - | 1199 | |
| TOR | 3287 - | 1219 | |
| LANS | 3308 - | 1240 | |
| BKC | 3535 - | 1467 | |
| SIMP | 3645 - | 1577 | |
| ARB | 3668 - | 1600 | |
| RTD | 3680 - | 1612 | |

API 15-163-22,287

8 5/8 " 216 / 135SX, 5 1/2 " 3676/150SX

NO DSTS

MICT - CO, PF (LKC) 3288-3430 OA, AC 8500G (28%), SWB LD,

SO, SET 2" TBG AT 3441', POP, P 4.2 BO & 76 BWPD, 4/23/84

INFO RELEASED: 8/9/84 - WAS TEMP ABD

NOTE: CORRECTION 3/1/84 - ORIGINALLY FIRST REPORTED IN
380'FNL & 330'FEL, SE/4

COPYRIGHT 1984
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS