

15-163-01878-0001

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-6-11-63
LEASE NAME Shepard "B"
WELL NUMBER 2

RECEIVED
STATE CORPORATION COMMISSION
9-16-88
SEP 16 1988

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

660 Ft. from S Section Line
660 Ft. from E Section Line

LEASE OPERATOR Lewis Bros. Oil Producers, Inc.
74172
ADDRESS One Williams Center, Suite 2000 Tulsa, OK

SEC. 23 TWP 10S RGE 18 ~~NE~~ or (W)
COUNTY Rooks

PHONE# (918) 584-3581 OPERATORS LICENSE NO. 5560

Date Well Completed 5-10-63

Character of Well Input Docket 83,056-C
(C-14,007)
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Commenced 7-20-88

Plugging Completed 7-20-88

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? _____ If not, is well log attached? No, attached to CP-1 6-28-88

Producing Formation Lansing/KC Depth to Top 3528 Bottom 3623 T.D. 3655

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing/KC	Oil, gas	3528	3623	8 5/8"	168	0
				4 1/2"	3654	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
Pumped in 4 1/2" casing 180 sks cement with 1/4# Flocele plus 3 sks hulls.
Max 350#. SI 350# psi. Pumped in 8 5/8" casing 60 sks cmt w/1/4# Flocele plus 3 sks hulls. Max 300#. SI 300#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B.J. Titan License No. _____

Address Hays, Kansas

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Douglas R. Lewis (Employee of Operator) or ~~Operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Douglas R Lewis
One Williams Center, Suite 2000
(Address) Tulsa, OK 74172

SUBSCRIBED AND SWORN TO before me this 14th day of September, 19 88
Melody M Sullivan
Notary Public

My Commission Expires: Aug. 6, 1989