

WELL PLUGGING RECORD


STATE OF KANSAS STATE CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 800 Bitting Building Wichita, Kansas

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

NORTH



Locate well correctly on above Section Plat

Rooks County. Sec. 23 Twp. 10 Rge. (E) 18 (W) Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. SW 1/4 of the NE 1/4 Lease Owner The Aylward Production Company Lease Name Shepard Well No. 1 Office Address 813 First National Bank Bldg., Wichita 2, Kansas Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole Date well completed November 22 1947 Application for plugging filed November 22 1947 Application for plugging approved November 22 1947 Plugging commenced November 22 1947 Plugging completed November 22 1947 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19. Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough, Hays, Kansas Producing formation None Depth to top Bottom Total Depth of Well 3891' Feet Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: Shale Flint Rock, Sandy Shale, 0, 150, 13" O.D., 150', None.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

LOWER PLUG

Tapered wood plug was pushed into 7-7/8" hole at bottom of surface pipe with bit, 2 drill collars and 3 joints 4 1/2" pipe. Plug was covered with rock, paper & burlap sacks. 20 Sacks cement was mixed in barrel on floor, poured in pipe. No fluid in pipe, washed down with water.

TOP PLUG

Pushed tree to 40' with Kelly covered with paper, burlap sacks and stone to 32 ft. Held weight of Kelly, mixed 15 sacks cement, poured on top of bridge to bottom of cellar.

12-6-47

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Aylward Production Company Address 813 First National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, N. W. Aylward (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) N.W. Aylward Hoisington, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 26th day of November, 19 47

My commission expires Apr. 6, 1951

My commission expires

Notary Public.



SHEPARD NO. 1

Casing Record:

Company: The Aylward Production Company, et al
Contractor: Aylward Drilling Company

Location:
SW 1/4 NE 1/4 of Sec.
23-10-18, Rooks Co.,
Kansas.
Elevation: 2143'
Potential: D & A

12 1/2" - 150'

Commenced: November 10, 1947
Completed: November 22, 1947

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Sandy Flint Rock	0	40	
Sandy Shale	40	160	
Shale & Shells	160	317	Set 12 1/2" casing @ 150'
Iron	317	693	Cemented with 100 sacks
Shale	693	720	
Sand	720	760	
Shale & Red Bed	760	820	
Sand	820	850	
Shale	850	1015	
Sand	1015	1175	
Sand Shale	1175	1250	
Shale Shells	1250	1375	
Shale & Red Bed	1375	1520	
Anhydrite	1520	1568	
Red Bed	1568	1600	
Pyrite Iron & Shale	1600	1670	
Shale	1670	1773	
Shale & Shells	1773	1955	
Salt	1955	1995	
Lime Broken	1995	2020	
Lime	2020	2185	
Lime & Shale	2185	2905	
Shale	2905	2964	
Lime	2964	2987	
Shale & Lime	2987	3130	
Shale	3130	3175	
Lime & Shale	3175	3409	
Lime	3409	3587	
Lime & Shale	3587	3729	
Shale	3729	3812	
Lime & Shale	3812	3891	

3891' T. D.

I hereby certify that this is a true and correct copy of the above log, to the best of my knowledge.

[Signature]

Subscribed and Sworn to before me this 2nd day of December, 1947.

[Signature]
Notary Public.



My commission expires Apr. 6, 1951

My commission expires: _____

PLUGGING
FILE SEC-23-T-10-R-18a
BOOK PAGE 7 LINE 8