

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-163-20-714-0000

LEASE NAME Eilers West

WELL NUMBER 1

SE NE NW
Ft. from S Section Line

Ft. from E Section Line

SEC. 27 TWP. 10 RGE. 18W (E) or (W)

COUNTY Rooks

Date Well Completed 9/14/77

Plugging Commenced 10/02/03

Plugging Completed 10/07/03

RECEIVED
10-14-03
OCT 14 2003
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR American Energies Corporation

ADDRESS 155 North Market, Suite 710, Wichita, KS

PHONE (316) 263-5785 OPERATORS LICENSE NO. 5399

Character of Well TA - Was Oil Well

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/7/03 (date)

by Richard Williams, District #4 (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? Sent with ACO-1

Producing Formation Arbuckle Depth to Top 3635 Bottom 3639 T.O. 3639

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface		221	0	8 5/8"	221	None
Production		3635	0	4 1/2"	3635	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging materials were used, state the character of same and depth placed, from feet to feet each section.

RU L.K. Wireline to unscrew tubing @ 1053', RU Swift cementing pumped 5 sx down surface pipe @ 600#. Hooked up to 2 3/8" tubing, mix and pump 75 sx. Circulated to surface. Unscrew tubing @ 1053' POH with tubing, recovered 34 jts. Mix and pump 170 sx down casing @ 1000# - Shut-In PSI: 600#.

Name of Plugging Contractor Swift Services, Inc. License No. 32382

Address P.O. Box 466, Ness City, KS 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: American Energies Corporation - Alan DeGood

STATE OF Kansas COUNTY OF Sedgwick, ss.

Alan L. DeGood, President - American Energies Corp. (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) Alan L. DeGood
Alan L. DeGood, President

(Address) 155 N. Market #710, Wichita, KS

SUBSCRIBED AND SWORN TO before me this 13th day of October, 19 2003

Melinda S. Wooten
Notary Public
Melinda S. Wooten

My Commission Expires: 3-12-04



15-163-20714-0000

RECEIVED

OCT 14 2003

KCC WICHITA

Gary Lindenmuth

508 W. 31st Street

Hays, Kansas 67601

785-625-8708
xmas@ruraltel.net

Fax 785-625-3733

October 7, 2003

Eilers West #1

October 2, 2003

R. U. Cheyenne Well Service, POH w/ 53 3/4 rods, ate into on #54. Pull on tubing, stuck in hole. SDFN

October 6, 2003

Pump down tubing, started circ. out of csg. Hole in csg. @ Braden head. Weld on slip collar, shut in csg. Pump down tubing 2 bpm @100# SD

October 7, 2003

RU L.K. wireline to unscrew tubing @ 1053'. RU Swift cementing, pump 5 sxs. Down surface pipe. @ 600#. Hook up to 2 3/8 tubing mix & pump 75 sxs. Circ. to surface. Unscrew tubing @ 1053' poh w/ tubing. recovered 34 jts. Mix & pump 170 sxs. Down csg. @ 1000# shut in psi 600#

Job comp. @ 3:00 P.M.
State man Richard



CHARGE TO: *American Energy Corporation*
 ADDRESS:
 CITY, STATE, ZIP CODE:

TICKET
 № 6033

PAGE 1 OF 1

1. SERVICE LOCATIONS <i>Hay</i>	WELL/PROJECT NO. <i>41</i>	LEASE <i>Eilers West</i>	COUNTY/PARISH <i>Rock</i>	STATE <i>K.</i>	CITY	DATE <i>10-7-03</i>	OWNER <i>Some</i>
2. TICKET TYPE <input type="checkbox"/> SERVICE <input type="checkbox"/> SALES	CONTRACTOR <i>Choy on Well Serv.</i>		RIG NAME/NO.	SHIPPED VIA <i>CEIT</i>	DELIVERED TO <i>Location</i>	ORDER NO.	
3. WELL TYPE <i>Oil</i>	WELL CATEGORY <i>Wbr/Power</i>	JOB PURPOSE <i>Plug To Abandon</i>		WELL PERMIT NO.	WELL LOCATION <i>Sec 20^s 10^s 18^s</i>		
4. REFERRAL LOCATION	INVOICE INSTRUCTIONS						

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		U/M		UNIT PRICE	AMOUNT
		LOC	ACCT	DF							
575		1			MILEAGE "103"	30	mi			2.50	75.00
576		1			Pump Service	1	hr			550.00	550.00
581		1			Service Charge	250	hr			1.00	250.00
583		1			Diagnose	550	hr			.85	467.50
329		1			60140 Per 10% Gel	250	hr			6.10	1525.00
275		1			Wells	0	hr			20.00	0.00

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

[Signature]
 TIME SIGNED A.M. P.M.

REMIT PAYMENT TO:
 SWIFT SERVICES, INC.
 P.O. BOX 466
 NESS CITY, KS 67560
 785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL	<i>2,867</i>	<i>50</i>
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?						
WE UNDERSTOOD AND MET YOUR NEEDS?						
OUR SERVICE WAS PERFORMED WITHOUT DELAY?						
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?				TAX		
ARE YOU SATISFIED WITH OUR SERVICE? <input type="checkbox"/> YES <input type="checkbox"/> NO				TOTAL		
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND						

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES The customer hereby acknowledges receipt of the materials and services listed on this ticket.

[Signature]
 APPROVAL

Thank You!

SWIFT Services, Inc.

DATE 10-7-03 PAGE NO. 1

Acme Energy WELL NO. 11 LEASE Eilers well JOB TYPE Plug To Abandon TICKET NO. 6038

PART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	11:00							on loc. set up record
	13:10							Hook up to 5 1/2" csg.
								Pump 2 3/4" 60/40R 10% C.C. SS
							600	Pro. to 600 psi tubing
								Hook up to 2 7/8" tubing
	13:15							Start mixing cur.
								Pumped 26 3/4" 75%.
								CIR calculated to surface
	13:30							Pull tubing out of hole
	14:10							Hook up to 4 1/2" csg.
		2					800	Pump 170SK down csg.
	14:35							Finished mixing. Heating 600 psi.
								shut in well head
								wash and pull up record

[Handwritten Signature]
10/7/03