

RECEIVED
10-14-03
OCT 14 2003

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Eilers - East
WELL NUMBER 1

LEASE OPERATOR American Energies Corporation

4290 Ft. from S Section Line
1650 Ft. from E Section Line

ADDRESS 155 North Market, Suite 710, Wichita, KS

SEC. 27 TWP. 10 RGE. 18W (E) or (W)

PHONE(S) (316) 263-5785 OPERATORS LICENSE NO. 5399

COUNTY Rooks

Character of Well TA - Was Oil Well

Date Well Completed 9/7/77

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Commenced 9/29/03

Plugging Completed 10/02/03

The plugging proposal was approved on 10/02/03 (date)

by Richard Williams (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? with ACO-1

Producing Formation Lansing Depth to Top 3456 Bottom 3462 T.D. 3651

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface		199'	0	8 5/8"	199'	None
Production		3646'	0	4 1/2"	3646'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other pl. were used, state the character of same and depth placed, from ___ feet to ___ feet each section.

RIH with tubing to 1085', RU Swift cementing, mix and pump 70 sx 60/40 poz with 10% gel down tubing and circ. to surface. POH w/ tubing. Mix and pump 50 sx 60/40 poz with 10% gel down casing 600#, 400#, Shut in PSI, shut well in. Hooked up to braden head mix and pump 25 sx, circulated around outside. Pump rest of 130 sx down casing.

Name of Plugging Contractor Swift Services, Inc. License No. 32382

Address P.O. Box 466, Ness city, KS 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: American Energies Corporation - Alan DeGood

STATE OF Kansas COUNTY OF Sedgwick, ss.


Alan L. DeGood, President - American Energies Corp. (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Alan L. DeGood
Alan L. DeGood, President
(Address) 155 N. Market #710, Wichita, KS

SUBSCRIBED AND SWORN TO before me this 13th day of October, 192003

Melinda S. Wooten
Notary Public
Melinda S. Wooten

My Commission Expires: 3-12-04



15-163-20730-0000

RECEIVED

OCT 14 2003

KCC WICHITA

Gary Lindenmuth
508 W. 31st Street
Hays, Kansas 67601

785-625-8708
xmas@ruraltel.net

Fax 785-625-3733

October 7 2003

Eilers East #1

September 29 2003

Moved in Cheyenne Well Service double drum @ rigged up. Ran sand pump to check TD @ 835'. Fluid down 50' from surface. Ran tar impression block, did not show anything. Ran sand pump w/no results. Ran 3 7/8" rock bit.

September 30, 2003

Tag bottom w/ bit @ 900' RU Cheyenne pump @ swivel clean out to 1065' POH w/ bit. Ran tar impression block, did not show anything. Ran 3 3/4" tapered mill, drilling iron sulfide w/ show of steel. SDFN

October 1 2003

Milling on iron sulfide & iron. POH w/mill & tubing. Pressure up on csg. pumping 1 1/2 bpm. @ 200 #. Spot 200 gal. 28% acid @ 1060'. POH w/ tubing and fill hole w/ water. SWI

October 2, 2003

RIH w/ tubing to 1085' RU Swift cementing. Mix & pump 70 sxs. 60/40 pozmix w/10% gel down tubing & circ. to surface. POH w/ tubing. Mix & pump 50 sxs. 60/40 poz. w/10% gel down csg. 600 # 400 # shut in psi. shut well in. Hook up to braden head mix & pump 25 sxs. Circ. around outside. Pump rest of cement 130 sxs. Down csg.

Job comp. @11:35 A.M.



CHARGE TO: American Energy
 ADDRESS:
 CITY, STATE, ZIP CODE:

TICKET
 No 6031

PAGE 1 OF 1

SERVICE LOCATIONS 1. <u>Haystack</u>	WELL/PROJECT NO.	LEASE <u>Wilens East</u>	COUNTY/PARISH <u>Reeds</u>	STATE <u>Ks</u>	CITY	DATE <u>10-2-03</u>	OWNER <u>Some</u>
2.	TICKET TYPE <input type="checkbox"/> SERVICE <input type="checkbox"/> SALES	CONTRACTOR <u>Cheyne Well Serv.</u>	RIG NAME/NO.	SHIPPED VIA <u>ET</u>	DELIVERED TO <u>Location</u>	ORDER NO.	
3.	WELL TYPE <u>Oil</u>	WELL CATEGORY <u>subsurface</u>	JOB PURPOSE <u>Plug To Abandon</u>	WELL PERMIT NO.	WELL LOCATION		
4. REFERRAL LOCATION	INVOICE INSTRUCTIONS						

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.	UM	QTY.	UM	UNIT PRICE	AMOUNT
		LOC	ACCT	DF							
575		1			MILEAGE "103	30	mi			2.30	73.00
576		1			Pump Service	1	hr			550.00	550.00
581		1			Service Charge	250	hrs			1.00	250.00
583		1			Drayage	447.5	mi			0.80	376.00
329		1			60/40 Pcs 10% Gel	250	hrs			6.10	1525.00
275		1			Hulls	6	hrs			30.00	180.00

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, **PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY** provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

[Signature]
 DATE SIGNED: TIME SIGNED: A.M. P.M.

REMIT PAYMENT TO:
 SWIFT SERVICES, INC.
 P.O. BOX 466
 NESS CITY, KS 67560
 785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL	2896.98
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?					
WE UNDERSTOOD AND MET YOUR NEEDS?					
OUR SERVICE WAS PERFORMED WITHOUT DELAY?					
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?				TAX	
ARE YOU SATISFIED WITH OUR SERVICE? <input type="checkbox"/> YES <input type="checkbox"/> NO				TOTAL	
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND					

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES The customer hereby acknowledges receipt of the materials and services listed on this ticket.

APPROVAL: *[Signature]*

Thank You!

