


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Rooks County. Sec. 26 Twp. 10S Rge. 18 (X) W (W)
Location as "NE/CNW%SW%" or footage from lines SE NW SW
Lease Owner Davis Bros.-Transit Corporation
Lease Name Shepard "K" Well No. 1
Office Address 1516 Liberty Bank Building, Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed March 13, 19 59
Application for plugging filed March 13, 19 59
Application for plugging approved March 13, 19 59
Plugging commenced March 13, 19 59
Plugging completed March 13, 19 59
Reason for abandonment of well or producing formation No production



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	161'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy drilling mud to 550'; set plug, cemented with 20 sacks cement
Filled hole with heavy drilling mud to 150'; set plug, cemented with 15 sacks cement
Filled hole with heavy drilling mud to 40'; set plug, cemented with 10 sacks cement to bottom of cellar

4-16-59
RECEIVED
STATE CORPORATION COMMISSION
APR 16 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Transit Corporation
Address 1516 Liberty Bank Building, Oklahoma City, Oklahoma

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.
Paul E. Gathers (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) Paul E. Gathers

SUBSCRIBED AND SWORN to before me this 14th day of April, 19 59
My commission expires May 17, 1962
Mildred [Signature]
Notary Public.

PLUGGING
FILE SEC. 26 T. 10 R. 18w
BOOK PAGE 24 LINE 34

DRILLER'S WELL LOG

Davis Bros. - Transit Corporation - Shepard "K" # 1 well located in
SE NW SW Section 26-10S-18W,
Rooks County, Kansas

Commenced: March 2, 1959
Completed: March 13, 1959
Elevation: 2076' KB

Casing 8 5/8" @ 161'
Cemented w/130 sacks

<u>Formation</u>	<u>From</u>	<u>To</u>
Surface clay	0	5
Post rock	5	40
Shale	40	85
Sand	85	115
Shale	115	161
Shale and shells	161	815
Sand	815	912
Shale and shells	912	1435
Anhydrite	1435	1466
Shale and shells	1466	1840
Shale	1840	2040
Lime and shale streaks	2040	2170
Salt and lime streaks	2170	2245
Lime and shale streaks	2245	2310
Lime	2310	2350
Shale and lime streaks	2350	2415
Shale	2415	2450
Shale w/lime streaks	2450	2502
Lime and shale	2502	2625
Shale and lime	2625	2920
Shale and lime streaks	2920	3020
Shale and lime	3020	3162
Lime	3162	3585
Lime and chert	3585	3654
Chert	3654	3675
Cherty conglomerate	3675	3763
Simpson shale	3763	3818
Arbuckle	3818	3846 TD

Summary of Formation

Anhydrite	1435'
Topeka	3068'
Heebner	3293'
Toronto	3310'
Lansing	3335'
Base of K.C.	3564'
Conglomerate	3599'
Simpson	3710'
Arbuckle	3818'

I hereby certify the foregoing to be a true and accurate Driller's Log of the formation encountered in the above well.

TRANSIT CORPORATION

Subscribed and sworn to before me
this 14th day of April, 1959.

BY Paul E. Gaskers

My Commission expires May 17, 1962.

Mildred Isom
Notary Public

RECEIVED
STATE COMMISSION
APR 16 1959
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 26 T. 10 R. 18W
BOOK PAGE 24 LINE 38