

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-23326-0000

LEASE NAME Eilers

WELL NUMBER 1

2,310 Ft. from S Section Line

380 Ft. from ^W Section Line

SEC. 27 TWP. 10 RGE. 18 (E) or (W)

COUNTY Rooks

Date Well Completed 6-30-01

Plugging Commenced 6-30-01

Plugging Completed 6-30-01

7-13-01
JUL 13 2001

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

CONSERVATION DIVISION

LEASE OPERATOR Black Petroleum Co.

ADDRESS PO Box 12922, Wichita, KS 67277-2922

PHONE# (316) 729-8220 OPERATORS LICENSE NO. 30407

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-30-01 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3,680'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	246'	Cmtd. w/160 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section. Push bridge plug to 10' above Arbuckle top, pump 25 sax cement on plug thru drill pipe. Push bridge plug to 1,460', pump 25 sax cement on plug thru drill pipe. Push bridge plug to 850', pump 100 sax cement on plug thru drill pipe. Push bridge plug to 300', pump 40 sax cement on plug thru drill pipe. Push bridge plug to 40', pump 10 sax cement on plug. Dump 15 sax cement down rat hole and 10 sax down mouse hole.

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address PO Box 709, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Black Petroleum Company

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas. (Employee of ~~Operator~~ or ~~XXXXXXXXXX~~) Contractor above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 9th day of July, 2001

My Commission Expires: _____

