

15-163-20043-0000
R


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. **30** Twp. **10S** Rge. **18W** (ASX) (W)
Location as "NE/CNWxSWx" or footage from lines. **NE SE SE**
Lease Owner. **D. R. Lauck Oil Company, Inc.**
Lease Name **Dauwe** Well No. **1**
Office Address **301 S. Broadway, Wichita, Kansas**
Character of Well (completed as Oil, Gas or Dry Hole) **Dry Hole**
Date well completed **August 10, 1967**
Application for plugging filed **August 10, 1967**
Application for plugging approved **August 10, 1967**
Plugging commenced **August 10, 1967**
Plugging completed **August 10, 1967**
Reason for abandonment of well or producing formation **Dry Hole**

If a producing well is abandoned, date of last production **19**
Was permission obtained from the Conservation Division or its agents before plugging was commenced? **Yes**

Name of Conservation Agent who supervised plugging of this well **Leo Massey**
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well **3682** Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0'	210'	8-5/8"	210'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3682'-800' Mud
800'-796' Plug
796'-756' Cement, 100 sacks
756'-210' Mud
210'-206' Plug
206'-166' Cement, 25 sacks
166'-40' Mud
40'-36' Plug
36'-6' Cement, 10 sacks (Bottom of Cellar)

8-22-67
AUG 22 1967
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor **Sun Cementing Co.**
Address **Great Bend, Kansas**

STATE OF **KANSAS**, COUNTY OF **SEDGWICK**, ss.
John H. Knightley (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) **John H. Knightley**
301 S. Broadway, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this **17th** day of **August**, 19**67**

My commission expires **March 12, 1971**

Stella J. Lippie
Notary Public.

15-163-20043-0000 PR

D. R. Lauck Oil Company, Inc.

Dauwe #1

NE SE SE Sec. 30-10S-18W
Rooks County, Kansas

Commenced: August 1, 1967
Completed: August 10, 1967

Casing Record: 210' 8-5/8" Cemented with 150 sacks Cement,
3 sacks Calcium Chloride.

Elevation: GL 2036, DF 2039, KB 2041.

Drillers Log

Tops

Surface Clay & post rock	40
Shale	645
Sand	800
Shale & Shells	890
Sand	1085
Shale & Shells	1401
Anhydrite	1438
Shale	1550
Shale & Shells	1950
Lime & Shale	2225
Shale & Lime	2460
Lime & Shale	2638
Shale & Lime	3030
Lime	3508
Shale & Lime	3540
Conglomerate	3612
Lime & Chert	3634
Arbuckle	3682 RTD

Sample	Welex
Heebner	3243-1202 3242-1201
Toronto	3256-1215 3256-1215
Lansing	3282-1241 3282-1241
Base Kansas City	3506-1465 3506-1465
Sand Conglomerate	3535-1494 3533-1492
Chert Conglomerate	3545-1504 3546-1505
Simpson Shale	3600-1559 3600-1559
Simpson Dolomite	3617-1576 3614-1573
Arbuckle	3634-1593 3635-1594
Total Depth	3682-1641 3681-1640

DST #1 (S) 3249-98, open 1 hour with weak blow 1 hour. Recovered 35' oil-cut mud. ISIP 940#, 30 min. FSIP 161#, 30 min. IFP 47#. FFP 57#.

DST #2 (S) 3316-55, open 20 minutes, weak blow 7 minutes, flushed tool. Recovered 20' oil-specked mud. ISIP 1014#, 30 min. FSIP 875#, 30 min. IFP 38#. FFP 47#.

DST #3 (S) 3360-3405, open 1 hour, good blow 1 hour. Recovered 300' gas and oil-cut muddy water (estimated 15% oil) and 720' water. ISIP 875#, 30 min. FSIP 792#, 30 min. IFP 95#. FFP 486#.

DST #4 (S) 3444-3508, open 20 minutes, weak blow 7 minutes, flushed tool. Recovered 15' oil-specked mud. ISIP 977#, 30 min. FSIP not recorded. IFP 57#. FFP 57#.

RECEIVED
STATE OF KANSAS COMMISSION

AUG 22 1967

CONSERVATION DIVISION
Wichita, Kansas

D&A