

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4

December 2003

Type or Print on this Form
Form must be Signed
blanks must be Filled

15-129-10219-00-01

Lease Operator: Anadarko Petroleum Corporation

Address: PO Box 1330 Houston, TX 77251-1330

Phone: (832) 636-1053 Operator License #: 4549

Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 05/9/2009 (Date)

by: Eric Maclaren (KCC District Agent's Name)

Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No

Producing Formation(s): List All (If needed attach another sheet)

Shawnee Group Depth to Top: 2729 Bottom: 2944 T.D. 3035'

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-129-10219-00-00

Lease Name: Switzer A

Well Number: 1

Spot Location (QQQQ): _____ - _____ - C - NW

1275 1320 Feet from ☒ North / ☐ South Section Line

1262 1320 Feet from ☐ East / ☒ West Section Line

Sec. 29 Twp. 34 S. R. 43 ☐ East ☒ West

County: Morton

Date Well Completed: 07/05/1961

Plugging Commenced: 05/09/2009

Plugging Completed: 05/10/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put in	Pulled out
RECEIVED JUN 26 2009 KCC WICHITA		0	566'	8-5/8"	566'	0
		0	3015'	4-1/2"	3015'	600'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from (bottom), to (top) for each plug set.

Mixed 100 lbs hulls & 15 sks cnt; pump plug from 2720' to 2525'. Tag plug @ 2517'. Pumped mud to 1200'.

Mix and pump 20 sks cnt from 1200' to 940'. Shot 4-1/2" csg @ 600'. Mix and pump 50 sks cnt from 600' to 450'.

Pull csg to 350'. Mix and pump 30 sks cnt from 350' to 250'. Pull csg to 40. Mix 10 sx cnt plug 40' to surface.

Cut off and capped 8-5/8" csg 3' below surface.

Name of Plugging Contractor: Sargent and Horton Plugging, Inc. License #: 31151


Address: Rt. 1 Box 49BA Tyrone, OK 73951-9731

Name of Party Responsible for Plugging Fees: Anadarko Petroleum Corporation

State of Texas County, Montgomery, ss.

Melanie Wiggins Regulatory Analyst

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well as filed and the same are true and correct, so help me God.



(Signature) Melanie Wiggins

(Address) PO Box 1330 Houston, TX 77251-1330

SUBSCRIBED and SWORN TO before me this 25th day of June, 2009

Cari B. Kirk

Notary Public

My Commission Expires: 11/21/10

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202