

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33392
Name: Keith F. Walker Oil & Gas Company, L.L.C
Address 1: 103 West Boyd Street
Address 2: _____
City: Norman State: OK Zip: 73069 + _____
Contact Person: Sonya King
Phone: (405) 701-0676
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Chester Depth to Top: 6398' Bottom: 6410' T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 119-20721-00-01
Spot Description: _____
SE NW NW Sec. 3 Twp. 35 S. R. 26 East West
990 Feet from North / South Line of Section
990 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Meade
Lease Name: Wyatt Ranch Well #: 3 #1R
Date Well Completed: 10/29/1985
The plugging proposal was approved on: 6/08/2009 (Date)
by: Steve Bond (KCC District Agent's Name)
Plugging Commenced: 06/05/2009
Plugging Completed: 06/09/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
<u>Chester</u>	<u>Gas</u>		<u>8 5/8"</u>	<u>1620'</u>	<u>0</u>
			<u>4 1/2"</u>	<u>6460'</u>	<u>2784'</u>

RECEIVED
JUN 29 2009
KCC WICHITA


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pumped 50 BBL mud down 4 1/2" csg. Ran CIBP on tbg. Set at 6332'. Pumped 10 sx of cement from 6332' to 6192'. Loaded 4 1/2" casing with mud & 200# cotton seed hulls. Cut 4 1/2" at 2784'. Laid down same. TIH with tubing. Spotted 50 sx at 1650' to 1482'. Spotted 50 sx at 900' to 732'. Spotted 50 sx of cement at 360' to 192'. Spotted 15 sx of cement at 40' to surface.

Plugging Contractor License #: 33311 Name: Phil Dollar Oilfield Services, Inc.
Address 1: P.O. Box 744 Address 2: _____
City: Perryton State: TX Zip: 79070 + 0744
Phone: (806) 435-3373

Name of Party Responsible for Plugging Fees: Keith F. Walker Oil & Gas Company, L.L.C.
State of Oklahoma County, Cleveland, ss.
Sonya King Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: _____


Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT