

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: # 5278  
Name: EOG RESOURCES, INC.  
Address 1: 3817 NW Expressway ; Suite 500  
Address 2: \_\_\_\_\_  
City: Oklahoma City State: OK Zip: 73112 + 1483  
Contact Person: Candy Driscoll  
Phone: (405) 246-3140  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
None Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. 5250'  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 119-20945 - 0000  
Spot Description: SW NW SW  
SW NWSW Sec. 23 Twp. 32 S. R. 26  East  West  
1,800 Feet from  North /  South Line of Section  
330 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Meade  
Lease Name: FLO 23 Well #: 1  
Date Well Completed: 4-21-95 9  
The plugging proposal was approved on: 6/10/2009 (Date)  
by: Steve Durant (KCC District Agent's Name)  
Plugging Commenced: 6/11/2009  
Plugging Completed: 6/15/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Chester	Dry	Surface	8 5/8"	917'	None
		Production	4 1/2"	5650'	1984'

RECEIVED  
JUL 06 2009  
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Load casing w/ drilling mud & set 4 1/2" CIBP @ 5405' , cap w/ 2 sks cement . Cut & pull 4 1/2" casing from 1984' . Run tubing to 1017' , mix & pump 100 sks Class "C" cement up to 648' . POH & WOC . Tag TOC @ 803' . Pull up hole @ 400' & spot 50 sks cement up to 225' . POH w/ tubing & top out 34' - 4' w/ 10 sks cement . Dig out & cut off 4' below ground level & weld ID plate .  
15

Plugging Contractor License #: 33338 Name: Orr Enterprises, Inc  
Address 1: PO Box 1706 Address 2: \_\_\_\_\_  
City: Runyan State: OK Zip: 73534 + \_\_\_\_\_  
Phone: (580) 251-9618  
Name of Party Responsible for Plugging Fees: EOG Resources, Inc.  
State of Oklahoma County, Oklahoma, ss.  
Candy Driscoll (Print Name)  Employee of Operator or  Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Candy Driscoll

PKT