

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5278
Name: EOG RESOURCES, INC.
Address 1: 3817 NW Expressway ; Suite 500
Address 2: _____
City: Oklahoma City State: OK Zip: 73112 + 1483
Contact Person: Candy Driscoll
Phone: (405) 246-3100
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet) 4
Krider Depth to Top: 2653' Bottom: 2673' T.D. 2674'
Herrington-Krider Depth to Top: 2625' Bottom: 2640' T.D. 2674'
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 175-00349 - 00 00
Spot Description: SW
_____ Sec. 27 Twp. 34 S. R. 33 East West
1,320 Feet from North / South Line of Section
1,320 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Seward
Lease Name: Oyler 27 Well #: 1
Date Well Completed: 9/02/1953
The plugging proposal was approved on: 6/09/2009 (Date)
by: Ken Gelick (KCC District Agent's Name)
Plugging Commenced: 6/29/2009
Plugging Completed: 6/30/2009

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface, Conductor & Production) | | | |
|---------------------------|---------|---|--------|---------------|------------|
| Formation | Content | Casing | Size | Setting Depth | Pulled Out |
| Herrington - Krider | Gas | Surface | 8 5/8" | 690' | None |
| | | Production | 5 1/2" | 2653' | None |
| | | | | | |
| | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

POH w/ rods & tbg , load csg w/ mud & set 5 1/2" CIBP @ 2575' , cap w/ 2 sks cement . Run tbg @ 1500' , mix & pump 80 sks class "C" cement up to 750' , POH w/ tbg @ 750' , mix & pump 70 sks ← 60 cement and circulate to surface , POH w/ tbg & top out w/ 10 sks cement . RU down 8 5/8" csg & fill w/ 1 sks cement at 200 psi . Dig out & cut off 4' below ground level & weld ID plate .

RECEIVED
JUL 09 2009

Plugging Contractor License #: 33338 Name: Orr Enterprises, Inc
Address 1: P.O. Box 1707 Address 2: _____
City: Duncan State: Oklahoma Zip: 73534 + 1706
Phone: (580) 467-0258

KCC WICHITA

Name of Party Responsible for Plugging Fees: EOG Resources
State of Oklahoma County, Oklahoma, ss.
Candy Driscoll
(Print Name) Employee of Operator or Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Candy Driscoll

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten signature]