

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

15-065-21133-00-00

Form CP-4

March 2009

Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5030
Name: VESS OIL CORPORATION
Address 1: 1700 Waterfront Parkway
Address 2: Bldg. 500
City: Wichita State: KS Zip: 67206 + _____
Contact Person: W.R. Horgan
Phone: (316) 682-1537 X102
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: D-19,636
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Cedar Hills Depth to Top: 1760 Bottom: 1790 T.D. 2000
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 15-065-21133 - 0001
Spot Description: SE SE SE
SE SE SE Sec. 29 Twp. 10 S. R. 24 East West
330 Feet from North / South Line of Section
330 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Graham
Lease Name: Hanna B Well #: #2
Date Well Completed: 8/16/79
The plugging proposal was approved on: 5/09 (Date)
by: Richard Williams-verbal (KCC District Agent's Name)
Plugging Commenced: 6/19/09
Plugging Completed: 6/19/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			8-5/8	278	-
			4-1/2	4018	-
			Perf 2050' w/	475 sx	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pumped down 4 1/2" casing w/195 sx 60/40 poz w/4% gel and 500# hulls at 800#. SI and holding 800#. Connected to 8 5/8" and pumped 5 sx same cement. SI - 250#. Approved by KCC (Pat Bedore)

Plugging Contractor License #: 5822 99996 Name: Allied Cement Co., Inc.
Address 1: P.O.Box 31 Address 2: _____
City: Russell State: KS Zip: 67665 + 0031
Phone: (785) 483-2627

Name of Party Responsible for Plugging Fees: Vess Oil Corporation
State of Kansas County, Sedgwick, ss.
Patrick T. Canaday Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: _____

Handwritten initials/signature

ALLIED CEMENTING CO., LLC. 037540

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Russey

DATE <i>10-19-09</i>	SEC. <i>29</i>	TWP. <i>10</i>	RANGE <i>24</i>	CALLED OUT	ON LOCATION	JOB START <i>9:30 AM</i>	JOB FINISH <i>10:30 AM</i>
LEASE <i>Hanna B</i>		WELL # <i>#2</i>	LOCATION <i>ST Peter 3S 3E</i>		COUNTY <i>GRAHAM</i>	STATE <i>KANSAS</i>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)			<i>1 E + N INTO</i>				

CONTRACTOR _____ OWNER _____

TYPE OF JOB *Plug Abandoned*

HOLE SIZE _____ T.D. _____

CASING SIZE *4 1/2* DEPTH *1760-*

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. *1760-1797*

DISPLACEMENT _____

CEMENT

AMOUNT ORDERED *200 SX 60/40 4% GEL*

500# Hulls

COMMON	<i>120</i>	SX	@	<i>13.50</i>	<i>1620.00</i>
POZMIX	<i>80</i>	SX	@	<i>7.55</i>	<i>604.00</i>
GEL	<i>8</i>	SX	@	<i>20.25</i>	<i>162.00</i>
CHLORIDE			@		
ASC			@		
<i>500# Hulls</i>			@	<i>31.05</i>	<i>155.25</i>
KANSAS CORPORATION COMMISSION			@		
			@		
			@		
			@		
			@		
			@		
			@		
HANDLING	<i>200</i>	SX	@	<i>2.25</i>	<i>450.00</i>
MILEAGE	<i>50</i>	Ton Mile	@	<i>.10¢</i>	<i>1000.00</i>
TOTAL					<i>3791.25</i>

EQUIPMENT

PUMP TRUCK CEMENTER *Glenn*

417 HELPER *MATT*

BULK TRUCK

344 DRIVER *Randy G.B.*

BULK TRUCK

_____ DRIVER _____

REMARKS:

4 1/2 CSG. mixed 25 SX STRAIGHT Cement, Followed By 100 SX cement & 500# Hulls. Shot in @ 800#, 85# BACKSIDE mixed 5 SX cement @ 250# MAX PSI. & Shot in. THANK'S

CHARGE TO: *Vess Oil Corporation*

STREET _____

CITY _____ STATE _____ ZIP _____

** STATE Rep Pat Padine (KCC) ON LOCATION*

SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE _____ *875.00*

EXTRA FOOTAGE @ _____

MILEAGE *50* @ *7.00* *350.00*

MANIFOLD @ _____

@ _____

@ _____

~~1008 1225.00~~ TOTAL *1225.00*

~~PLUG & FLOAT EQUIPMENT~~

To Allied Cementing Co., LLC.

You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME _____

SIGNATURE *[Signature]*

@ _____

@ _____

@ _____

@ _____

TOTAL _____

SALES TAX (If Any) _____

TOTAL CHARGES _____

DISCOUNT _____ IF PAID IN 30 DAYS

~~1008 1225.00~~ ~~PLUG & FLOAT EQUIPMENT~~

JUL 17 1979

CONTRACTOR'S WELL LOG

OPERATOR: Tomlinson Oil Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: HANNA "B" #2
 LOCATION: SE SE SE, Section 29-10S-24W
 Graham County, Kansas
 SPUD DATE: July 03, 1979
 COMPLETION DATE: July 11, 1979

0	151	Surface sand and clay
151	1961	Sand and shale
1961	2037	Shale
2037	2075	Anhydrite
2075	3074	Shale
3074	3241	Shale and lime
3241	3736	Lime and shale
3736	3808	Lime
3808	3842	Lime and shale
3842	3870	Lime
3870	3945	Lime and shale
3945	3974	Lime
3974	4020	Lime and shale
	4020	Rotary Total Depth

KANSAS CORPORATION COMMISSION

JUL 10 2009
RECEIVED

Spud hole at 1:45 p.m., July 03, 1979. Drilled 287' of 12¼" hole. Ran 7 joints of 8-5/8" - 20# new 8rd thd casing. Set at 285' with 225 sacks of common cement, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 7:00 p.m., July 03, 1979.

T.D. 4020'. Ran 118 joints of 4½" - 9½# 8rd thd casing. Set at 4018' with 125 sacks of common cement, salt saturated. Flushed with 10 bbls. of salt flush. Job was complete at 3:35 p.m., 7-11-79.

SAMPLE TOPS:

Anhydrite 2037'
 B/Anhydrite 2075'


STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Hanna "B" #2, SE SE SE, Section 29-10S-24W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 16th day of July, 1979.



Sherrie L. Brooks
 Sherrie Brooks, Notary Public

My commission expires 8-21-82.