

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 33392  
Name: Keith F. Walker Oil & Gas Company, L.L.C  
Address 1: 103 West Boyd Street  
Address 2: \_\_\_\_\_  
City: Norman State: OK Zip: 73069 + \_\_\_\_\_  
Contact Person: Sonya King  
Phone: (405) 701-0676  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Chester Depth to Top: 5358' Bottom: 5405' T.D. 5966'  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 119-20037-00-01  
Spot Description: \_\_\_\_\_  
- - - NE NW Sec. 29 Twp. 30 S. R. 29  East  West  
660 Feet from  North /  South Line of Section  
1.980 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Meade  
Lease Name: Weaver Well #: 29 #1R  
Date Well Completed: 10/05/2008  
The plugging proposal was approved on: 03/25/2009 (Date)  
by: Steve Bond (KCC District Agent's Name)  
Plugging Commenced: 06/12/2009  
Plugging Completed: 06/15/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
	Gas		8 5/8"	1742'	0
			4 1/2"	5966'	2801'

RECEIVED  
JUN 29 2009  
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pumped 50 BBL mud down 4 1/2" csg. Ran CIBP on tbg. Set at 5298'. Pumped 10 sx of cement from 5298' to 5158'. Loaded 4 1/2" casing with mud & 200# cotton seed hulls. Cut 4 1/2" at 2801'. Laid down same. TIH with tubing. Spotted 50 sx at 1770' to 1602'. Spotted 40 sx at 600' to 466'. Spotted 20 sx of cement at 40' to surface.

Plugging Contractor License #: 33311 Name: Phil Dollar Oilfield Services, Inc.  
Address 1: P.O. Box 744 Address 2: \_\_\_\_\_  
City: Perryton State: TX Zip: 79070 + 0744  
Phone: (806) 435-3373

Name of Party Responsible for Plugging Fees: Keith F. Walker Oil & Gas Company, L.L.C.  
State of Oklahoma County, Cleveland, ss.  
Sonya King (Print Name)  Employee of Operator or  Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: \_\_\_\_\_

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PCT