

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

WELL PLUGGING RECORD

K.A.R. 82-3-117

Lease Operator: Anadarko Petroleum Corporation
Address: PO Box 1330 Houston, TX 77251-1330
Phone: (832) 636-8380 Operator License #: 4549
Type of Well: Gas Docket #:
The plugging proposal was approved on: 05/29/2009 (Date)
by: Richard Lacey (KCC District Agent's Name)
Is ACO-1 filed? [x] Yes [] No If not, is well log attached? [] Yes [] No
Producing Formation(s): List All (If needed attach another sheet)
Lower Chester Depth to Top: 5904 Bottom: 5910 T.D. 6350'

API Number: 15- 175-20583-00-00
Lease Name: Hitch J
Well Number: 1-5
Spot Location (QQQQ): nesw - W2 - NE - SW
1900 Feet from [] North / [x] South Section Line
1800 Feet from [] East / [x] West Section Line
Sec. 5 Twp. 33 S. R. 34 [] East [x] West
County: Seward
Date Well Completed: 02/27/1982
Plugging Commenced: 06/01/2009
Plugging Completed: 06/02/2009

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put in, Pulled out. Contains data for oil and gas formations.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Mixed 200 lbs hulls & 20 sks cmt; pump plug from 5904' to 5704'. Shot 4.5" csg @ 2507'. Shot again @ 1840' Pulled to 1690'. Circ mud, mix and pump 50 sks cmt from 1690' to 1540'. Pull csg to 600'. Mix and pump 40 sks cmt from 600' to 480'. Pull csg to 40'. Mix and pump 10 sks cmt from 40' to surface. Cut off and capped 8-5/8" csg 3' below surface.

Name of Plugging Contractor: Sargent and Horton Plugging, Inc. License #: 31151

Address: Rt. 1 Box 49BA Tyrone, OK 73951-9731

Name of Party Responsible for Plugging Fees: Anadarko Petroleum Corporation

State of Texas County, Montgomery, ss.

Diana Smart Staff Regulatory Analyst (Employee of Operator) or (Operator) on above-described well, being first duly


sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Diana Smart

(Address) PO Box 1330 Houston, TX 77251-1330

SUBSCRIBED and SWORN TO before me this 22nd day of June, 2009

Handwritten signature of Cynthia Rodriguez



My Commission Expires: Nov 9, 2010

KANSAS CORPORATION COMMISSION

JUN 23 2009

RECEIVED

Handwritten initials