

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 32679
Name: AAS Oil Company, Inc
Address 1: 2508 Edgemont Drive
Address 2: _____
City: Arkansas City State: Ks Zip: 67005 + _____
Contact Person: Gary Anstine
Phone: (620) 441-8165
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: E-19540 Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
mississippi Depth to Top: 3353 Bottom: 3370 T.D. 3370
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 191-10370-0001
Spot Description: _____
NW SW NW Sec. 34 Twp. 32 S. R. 2 East West
3,630 Feet from North / South Line of Section
4,950 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Sumner
Lease Name: Nofsinger Dobbins Well #: 1
Date Well Completed: 6/01/60
The plugging proposal was approved on: 6/04/09 (Date)
by: Steve VanGieson (KCC District Agent's Name)
Plugging Commenced: 6/04/09
Plugging Completed: 6/04/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
mississippi	water	surface	8.625"	185'	0
		production	4.5"	3353'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 2" tubing to 1780', hole was full of Drilling mud spotted 20 sacks 60-40 pos-mix w/3% cal.chloride pulled tubing to 918' waited 1 hour tagged top of cement @ 1100'.spotted 20 sacks 60-40 pos mix w/3% cal.chloride @ 918' pulled tubing Waited 1hour . Tagged top of Cement @ 903' .perforated 4.5" casing @ 250' ran 2" to 250' and circulated cement to surface. cut pipe off 6' below ground level and welded on cap .

Plugging Contractor License #: 31539 Name: SAM'S Well Service
Address 1: PO Box 2444 Address 2: _____
City: Ponca City State: OK Zip: 74602 + 2444
Phone: (620) 441-3943
Name of Party Responsible for Plugging Fees: AAS Oil Company, Inc
State of Ks County, Cowley, ss.
Gary Anstine
(Print Name) Employee of Operator or Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: _____

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PPT