

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Cabot Oil & Gas Corporation  
Address: 600 17th Street, Ste. 900N, Denver, CO  
Phone: (303) 226-9443 Operator License #: 6120  
Type of Well: Oil Gas KCCPT PERCP 213 Docket #: NA  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 6-11-09 (Date)  
by: Jack MacLaskey (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
St. Louis Depth to Top: 5,650' Bottom: 5,740' T.D. 5,830'  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 175-21498 - 00 00  
Lease Name: Johnson  
Well Number: 5-17  
Spot Location (QQQQ): C - SE - SE - NW  
2310 Feet from  North /  South Section Line  
2310 Feet from  East /  West Section Line  
Sec. 17 Twp. 32 S. R. 33  East  West  
County: Seward  
Date Well Completed: 12-11-95  
Plugging Commenced: 6-15-09  
Plugging Completed: 6-16-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Chester	Dry	54'	0'	20"	54'	0'
St. Louis	Oil	1,525'	0'	8-5/8"	1,525'	0'
		5,828'	0'	5-1/2"	5,828'	2,409'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.  
Pumped 25 sx cement from 4,918'-4,718'. Placed mud from 4,718'-1,550'. Pulled 5 1/2" csg from 2,409'-0'. Spotted cement plug from 1,550' to 1,400' with 50 sx cement. Mud spotted from 1,400'-550'. Spotted 40 sx cement from 550'-430' and 10 sx cement plug from 40' - ground level. Cut off and capped casing 3' below ground level.

RECEIVED

Name of Plugging Contractor: Sargent & Horton Plugging, Inc. License #: 31151  
Address: Rt. 1, Box 49 BA, Tyrone, OK 73951-9731

JUN 19 2009

Name of Party Responsible for Plugging Fees: Cabot Oil & Gas Corporation, 600 17th St., Ste. 900N  
State of Colorado County, Denver, ss.

KCC WICHITA

Robert Balcer (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

MONICA JAMISON  
NOTARY PUBLIC  
STATE OF COLORADO  
My Commission Expires 12-03-2012

(Signature) Robert Balcer  
(Address) 600 17th Street, Ste. 900N, Denver, CO 80202

Subscribed and SWORN TO before me this 18 day of June, 2009  
Monica Jamison My Commission Expires: 12-03-2012  
Notary Public

Handwritten initials/signature.