

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

009-00357-0000
4/20/51

OPERATOR: License #: 5920
Name: TE-PE OIL & GAS
Address 1: P.O. BOX 522
Address 2: _____
City: CANTON State: KS Zip: 67428 + 0522
Contact Person: TERRY P BANDY
Phone: (620) 628-4428
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
LKC Depth to Top: 3077 Bottom: 3270 T.D. _____
TOPEKA Depth to Top: 2705 Bottom: 2970 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 4/20/51
Spot Description: C NE NE SW
C NE NE SW Sec. 31 Twp. 17 S. R. 12 East West
2,310 Feet from North / South Line of Section
2,310 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: BARTON
Lease Name: W.M. EVELEIGH Well #: 1
Date Well Completed: 4/20/51
The plugging proposal was approved on: _____ (Date)
by: CASE MORRIS (KCC District Agent's Name)
Plugging Commenced: 6/3/09
Plugging Completed: 6/8/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
LKC	OIL & WATER	SURFACE	8-5/8"	706	0
		PRODUCTION	5-1/2"	3430	0

RECEIVED
JUN 18 2009
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Stem in valve was broke; Unscrewed and blew out oil. Bridge plug set at 2880'. Bailed 2 sacks cement on plug. Ripped casing at 1530'. Pulled up: Casing was welded on top and bottom of collar. Pumped 150 sacks; 300# hulls at 1500'. Perforated 5-1/2" at 575'. Pumped 230 sacks. Didn't get cement to circulate. Tagged cement at 130'. Ran 1" down 8-5/8" to 130'; Pumped 40 sacks to surface. Ran 1" down 5-1/2"; Pumped 20 sacks to surface.

Plugging Contractor License #: 31925 Name: QUALITY WELL SERVICE
Address 1: 190 US HWY 56 Address 2: _____
City: ELLINWOOD State: KS Zip: 67526 + _____
Phone: (620) 938-2388
Name of Party Responsible for Plugging Fees: TE-PE OIL & GAS
State of KANSAS County, MCPHERSON, ss.
TERRY P. BANDY Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Terry Bandy

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]