

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5254
Name: MIDCO Exploration, Inc.
Address 1: 414 Plaza Drive, Suite 204
Address 2: _____
City: Westmont State: IL Zip: 60559 + 1265
Contact Person: Earl J. Joyce, Jr.
Phone: (630) 655-2198
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Mississippi Depth to Top: 4117' Bottom: 4122 T.D. 4122
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 095-20488-0000
Spot Description: _____
C NW Sec. 35 Twp. 28 S. R. 8 East West
1,320 Feet from North / South Line of Section
1,320 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Kingman
Lease Name: Ramsey O m Well #: 1
Date Well Completed: 6/28/1976
The plugging proposal was approved on: 5/7/09 (Date)
by: Steve Vangiesen (KCC District Agent's Name)
Plugging Commenced: 5/7/09
Plugging Completed: 5/14/09

KCC PKT Per CP 2/3

KCC PKT Per CP 2/3

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8	208	0
		Production	4 1/2"	4115	0

RECEIVED
JUN 16 2009
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

5/7 - Set cast iron bridge plug at 4090' ; dump 2 sacks cement; ran a cased hole bond log; perforate @ 1250, 1500 and 1900, but could not pump cement in. Shut down - Steve Vangiesen on location.
5/13 - Run tubing to 1961' and circulate 75 sacks; pull tubing to 960' ; reverse out 6 barrels; pressure well up to 800 lbs. (held); circulate around with 80 sacks; top well off with 15 sacks
5/14 - Cement staged at surface; dug up and cut casing at 4 1/2' ; filled hole; B.J. Hope on location.

Plugging Contractor License #: 7023 Name: Klima Well Service, Inc.
Address 1: PO Box 48 Address 2: _____
City: Great Bend State: KS Zip: 67530 + _____
Phone: (620) 793-8888
Name of Party Responsible for Plugging Fees: MIDCO Exploration, Inc.
State of Illinois County, DuPage, ss.
Earl J. Joyce, Jr. Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: _____

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT