

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Eagle Creek Corporation

Address: 150 N. Main Ste. 905 Wichita KS

Phone: (316) 264 8044 Operator License #: 30129

Type of Well: Gas Docket #: _____
(Oil, Gas Q&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 6-1-09 (Date)

by: Steve Durrant (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

ATOKA Depth to Top: 5602 Bottom: 5605 T.D. _____

KANSAS CITY Depth to Top: 4874 Bottom: 4879 T.D. _____

COUNCIL GROVE Depth to Top: 3119 Bottom: 3259 T.D. _____

API Number: 15-119-20834-0001

Lease Name: Ross

Well Number: 5-17

Spot Location (QQQQ): _____ - _____ - NE - SW

1980 Feet from North / South Section Line

1980 Feet from East / West Section Line

Sec. 17 Twp. 34 S. R. 28 East West

County: Meade

Date Well Completed: 6-30-1991

Plugging Commenced: 6-5-09

Plugging Completed: 6-5-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	1624	-
<u>ATOKA</u>	<u>LIME</u>	<u>5602</u>	<u>5605</u>	5 1/2	5686	2417
<u>KANSAS CITY</u>	<u>LIME</u>	<u>4874</u>	<u>4879</u>			
<u>COUNCIL GROVE</u>	<u>LIME</u>	<u>3119</u>	<u>3259</u>			

RECEIVED
JUN 25 2009
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 300 lb. hulls + 25 sx cmt. to plug perms from 3119 to 2919. Shot + pulled 5 1/2 to 1650. Circ. hole w/mud. Mixed 50 sx plug 1650 to 1500 40 sx 600 to 480 10 sx 40-0 Capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151

Address: Rt. 1, Box 49 BA Tyrone, OK 73951-9731

Name of Party Responsible for Plugging Fees: EAGLE CREEK CORPORATION

State of KANSAS County, SEDGWICK, ss.

DAVID CALLEWAERT (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) [Signature]

(Address) 150 N. MAIN #905 WICHITA, KS 67202

SUBSCRIBED and SWORN TO before me this 24th day of JUNE, 2009

[Signature] My Commission Expires: 4/28/09
Notary Public

Debra R. Stoddard
Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



[Handwritten initials]