

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 31739
Name: luka-Carmi Development, LLC
Address 1: PO Box 907
Address 2: _____
City: Pratt State: KS Zip: 67124 + _____
Contact Person: Kenneth C. Gates
Phone: (620) 672-9571 Ext 5
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: 4180 Bottom: 4200 T.D. 4337
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 151-10232-00-00
Spot Description: _____
N/2 .N/2. NE Sec. 18 Twp. 27 S. R. 12 East West
330 Feet from North / South Line of Section
1,215 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Pratt
Lease Name: SICU (Seidel) Well #: 8 (#3)
Date Well Completed: 04-1955
The plugging proposal was approved on: 1-16-2009 (Date)
by: Steve Bond (KCC District Agent's Name)
Plugging Commenced: 06-16-2009
Plugging Completed: 6-18-2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	787'	
		Production	5 1/2"	4336'	1474'

RECEIVED
JUN 26 2009
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set bridge plug at 4120' with 2 sacks cement. Shot off casing at 1474' - pulled 20 joints. Ran 12 sacks gel and 50 sacks 60/40 poz at 819'. Pulled 13 joints. Ran 50 sacks 60/40 poz at 403'. Pulled 13 joints. Ran 1 joint back with 10 sacks 60/40 poz at 40' - solid to surface.

Plugging Contractor License #: 5893 Name: Pratt Well Service, Inc.
Address 1: PO Box 907 Address 2: _____
City: Pratt State: KS Zip: 67124 + _____
Phone: (620) 672-9571 ext 5
Name of Party Responsible for Plugging Fees: Pratt Well Service, Inc. Luka-Carmi Development LLC
State of Kansas County, Pratt, ss.
Kenneth C. Gates
(Print Name) Employee of Operator or Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: Kenneth C. Gates

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCC
PRT

[Handwritten signature]



PAGE 1 of 1	CUST NO 1001991	INVOICE DATE 06/22/2009
INVOICE NUMBER 1718 - 90057952		

Pratt (620) 672-1201

B IUKA-CARMI DEVELOPMENT LLC
 I PO Box: 907
 L PRATT
 L KS US 67124
 T
 O ATTN:

J LEASE NAME Seidel 3
 O LOCATION
 B COUNTY Pratt
 S STATE KS
 I JOB DESCRIPTION Cement-Casing Seat-Prod W
 T JOB CONTACT
 E

51011 #8

JOB #	EQUIPMENT #	PURCHASE ORDER NO.	TERMS	DUE DATE	
40051284	19905		Net - 30 days	07/22/2009	
For Service Dates: 06/17/2009 to 06/17/2009					
0040051284					
171800208A Cement-Casing Seat-Prod W 06/17/2009					
Cement		110.00	EA	9.00	990.00 T
60/40 POZ					
Additives		1,390.00	EA	0.19	260.62 T
Cement Gel					
Mileage		10.00	MI	5.25	52.50 T
Heavy Equipment Mileage					
Mileage		125.00	MI	1.20	150.00 T
Proppant and Bulk Delivery Charge					
Mileage		110.00	MI	1.05	115.50 T
Blending & Mizing Service Charge					
Pickup		5.00	HR	3.19	15.94 T
Unit Mileage Charge-Pickups, Vans & Cars					
Pump Charge-Hourly		1.00	HR	750.00	750.00 T
Depth Charge; 0-500'					
Supervisor		1.00	HR	131.25	131.25 T
Service Supervisor Charge					

RECEIVED
 JUN 26 2009
 KCC WICHITA

PLEASE REMIT TO:	SEND OTHER CORRESPONDENCE TO:	SUB TOTAL	2,465.81
BASIC ENERGY SERVICES, LP	BASIC ENERGY SERVICES, LP	TAX	155.35
PO BOX 841903	PO BOX 10460	INVOICE TOTAL	2,621.16
DALLAS, TX 75284-1903	MIDLAND, TX 79702		