

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Charles N. Griffin
 Address: P.O. Box 127
 Phone: (720) 490 - 5648 Operator License #: 33936
 Type of Well: Gas Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: _____ (Date)
 by: Steve Pfeifer (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (if needed attach another sheet)
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 151-11026 - 00 00
 Lease Name: Schrack
 Well Number: #1
 Spot Location (QQQQ): _____ - _____ - SW - SE
660 Feet from North / South Section Line
1980 Feet from East / West Section Line
 Sec. 11 Twp. 27 S. R. 15 East West
 County: Pratt
 Date Well Completed: 7/26/1962
 Plugging Commenced: 6/18/09
 Plugging Completed: 6/22/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	300'	none
				4 1/2	4655'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Bailer got stuck in hole, Perforated casing 820, push bailer to 1395', ran 2 3/8 tubing to 1000', pumped 300 sacks of cement, perforated 330', Ran tubing to 350', and circulated 35 sacks to surface. Pumped 80 sacks of cement and circulated out of surface pipe, topped off with 10 sacks. 60/40 pos, 4% gel. Plugging complete.

Name of Plugging Contractor: Mike's Testing and Salvage Inc. License #: 31529
 Address: P.O. Box 467 Chase Kansas 67524

RECEIVED

JUN 30 2009

Name of Party Responsible for Plugging Fees: Charles N. Griffin
 State of Kansas County, Rice, ss.

KCC WICHITA


Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) *Mike Kelso*
 (Address) P.O. Box 467 Chase Kansas 67524

SUBSCRIBED and SWORN TO before me this 23rd day of June, 2009

Irene Herzberg
 Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PCT