

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Popp Operating, Inc.
Address: P.O. Box 187, Hoisington, KS 67544-0187
Phone: (620) 786-5514 Operator License #: 32325
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Case Morris (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Platt Depth to Top: 2858' Bottom: 2862' T.D. _____
Arb Depth to Top: 3276' Bottom: 3278.5' T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-009-24734-0000
Lease Name: Panning
Well Number: #4
Spot Location (QQQQ): S/2 - N/2 - N/2 - SW
2310 Feet from North / South Section Line
1320 Feet from East / West Section Line
Sec. 11 Twp. 20 S. R. 11 East West
County: Barton
Date Well Completed: _____
Plugging Commenced: 06/01/09
Plugging Completed: 06/03/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	499'	
				5 1/2"	3,375'	1,860'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand was 2,800'. Bailed 5 sacks cement with bailer. Had 16" stretch. Ripped casing at 2,010'. Ripped casing at 1,860'. Pulled casing to 1,500'. Pumped 150 sacks; 300# hulls. Pulled to 500'. Pumped 50 sacks; 100# hulls. Pulled to 200'. Circulated with 65 sacks to surface.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925
Address: 190 US Highway 56, Ellinwood, KS 67526
Name of Party Responsible for Plugging Fees: Popp Operating, Inc.
State of Kansas County, Barton, ss.

RECEIVED


JUN 3 8 2009

KCC WICHITA

Rickey Popp (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Rickey Popp

(Address) P.O. Box 187 Hoisington, Ks 67544



Subscribed and SWORN TO before me this 29th day of June, 2009
Jane M. Steinert My Commission Expires: 5/20/2011
Notary Public

PT

Quality Well Service, Inc.

190 US Highway 56
Ellinwood, KS 67526

Invoice

Date	Invoice #
6/15/2009	1086

Bill To
Popp Operating, Inc. Box 187 Hoisington, KS 67544

P.O. No.	Terms	Lease Name
	net	Panning #4

Description	Qty	Rate	Amount
Rig Time	19	185.00	3,515.00T
Floor Rental	1	125.00	125.00T
Sand	1	35.00	35.00T
Cement	5	9.00	45.00T
Shots	2	300.00	600.00T
Water Truck	5	75.00	375.00T
Backhoe	3	75.00	225.00T
Phone Calls	1	15.00	15.00T
Clerical	1	20.00	20.00T
Wiping Rubber	1	20.00	20.00T
Fresh Water	1	20.00	20.00T
06/01/09: Drove to location. Backed ring in and raised pole. Drove home.			
06/02/09: Drove to location and check hole. Sanded off bottom; Loaded hole with water. Dug cellar; Unpacked casing head. Set floor. Checked hole; Sand was at 2,800'. Bailed 5 sacks cement with bailer. Pulled slips; Had 16" stretch. Ripped casing at 2,010'; Worked pipe. Ripped casing at 1,860'; Pipe came free. Swedge in. Drove home.			
06/03/09: Drove to location. Pulled casing up to 1,500'. Pumped 150 sacks; 300# hulls. Pulled to 500'; Pumped 50 sacks; 100# hulls. Pulled to 200'; Circulated with 65 sacks to surface. Pulled rest of casing. Tore down floor and rig. Cleaned up location.			
Subtotal			\$4,995.00
Sales Tax (6.55%)			\$327.17
Total			\$5,322.17

RECEIVED
JUN 30 2009
KCC WICHITA

Quality Oilwell Cementing Inc.

Invoice

740 W WICHITA
 P.O. Box 32
 Russell, KS 67665

Date	Invoice #
6/5/2009	1635

Bill To
Popp Operating P.O. Box 187 Hoisington Ks 67544

P.O. No.	Terms	Project
	Net 30	

Quantity	Description	Rate	Amount
159	common	10.00	1,590.00T
106	POZ	6.00	636.00T
10	GEL	17.00	170.00T
4	hulls	25.00	100.00T
279	handling	1.75	488.25T
1	MILEAGE CHARGE	300.00	300.00T
1	pump truck charge plugging	500.00	500.00T
15	pump truck mileage charge	6.00	90.00T
775	discount 20% if paid within 30 days DISCOUNT HAS ALREADY BEEN DEDUCTED	-1.00	-775.00T
	LEASE: PANNING WELL #4 Barton county Sales Tax	6.30%	195.25

6 RCV'D 6-10-09
 Lease Panning
 Acct # _____
 Date PD/Ck # _____
 Material - \$ 2122.44
 Labor - \$ 1172.06

RECEIVED
 JUN 30 2009
 KCC WICHITA

Thank you for your business. Dave	Total	\$3,294.50
-----------------------------------	--------------	------------