

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
March 2009  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 33608  
Name: W. D. Short Oil Co. LLC  
Address 1: P.O. Box 729  
Address 2: 102 S. River Rd.  
City: Oxford State: Ks Zip: 67119 + 0729  
Contact Person: William D. (Don) Short Jr.  
Phone: ( 620 ) 455-3576

API No. 15 - 035-01124 <sup>02124-0000</sup>  
If pre 1967, supply original completion date: 4-16-1963  
Spot Description: SW-SESE Sec. 2 Twp. 34 S. R. 5 ☒ East ☐ West  
320 <sup>360</sup> Feet from ☐ North / ☒ South Line of Section  
990 <sup>1090</sup> Feet from ☒ East / ☐ West Line of Section  
Footages Calculated from Nearest Outside Section Corner: KCC PKT  
☐ NE ☐ NW ☒ SE ☐ SW  
County: Cowley  
Lease Name: Hart Well #: 4

Check One: ☒ Oil Well ☐ Gas Well ☐ OG ☐ D&A ☐ Cathodic ☐ Water Supply Well ☐ Other: \_\_\_\_\_  
☐ SWD Permit #: \_\_\_\_\_ ☐ ENHR Permit #: \_\_\_\_\_ ☐ Gas Storage Permit #: \_\_\_\_\_  
Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks  
Surface Casing Size: 8-5/8" Set at: 230' Cemented with: 175sx Sacks  
Production Casing Size: 4-1/2" Set at: 3112' Cemented with: 125sx Sacks  
List (ALL) Perforations and Bridge Plug Sets:

Elevation: 1241 ( ☐ G.L. / ☒ K.B. ) T.D.: 3133 PBTD: \_\_\_\_\_ Anhydrite Depth: Unknown  
(Stone Corral Formation)  
Condition of Well: ☒ Good ☐ Poor ☐ Junk in Hole ☐ Casing Leak at: \_\_\_\_\_  
(Interval)  
Proposed Method of Plugging (attach a separate page if additional space is needed):

**Per KCC Instructions**

Is Well Log attached to this application? ☒ Yes ☐ No Is ACO-1 filed? ☒ Yes ☐ No  
If ACO-1 not filed, explain why:

KANSAS CORPORATION COMMISSION  
JUL 29 2009  
RECEIVED

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Mike Anstine  
Address: P.O. Box 729, 102 S. River Rd. City: Oxford State: Ks Zip: 67119 + 0729  
Phone: ( 620 ) 218-1822  
Plugging Contractor License #: 34271 Name: Kivett Plugging  
Address 1: P.O. Box 134 Address 2: 402 N. 13th St.  
City: Blackwell State: Ok Zip: 74631 + 0134  
Phone: ( 580 ) 763-7748  
Proposed Date of Plugging (if known): Aug. 14, 2009

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: July 27, 2009 Authorized Operator / Agent: [Signature] (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

DIS + 2  
PKT

DRILLERS' LOG  
SUN OIL COMPANY  
J. A. HART #4  
SW/4 SE/4 SE/4  
Sec. 2, Twp. 34S, Rge. 5E  
Cowley County, Kansas

<u>Formation</u>	<u>From</u>	<u>To</u>		
Lime and shale	0	506	Drilling Commenced	4-15-63
Shale w/l.s. strks.	506	1142	Drilling Completed	4-25-63
Lime w/sh. strks.	1142	1234		
Shale and lime	1234	1340	<u>CASING RECORD:</u>	
Lime w/strks. shale	1340	1628	8-5/8" at 230' w/175 sax	
Shale and lime	1628	2346		
Lime	2346	2440	4 1/2" at 3112' w/125 sax.	
Shale	2440	2488		
Kansas City Lime	2488	2592		
Shale and lime	2592	2726		
Marmaton Lime	2726	2856	Rotary drilled 0-3133' T.D.	
Shale and lime	2856	3110		
Miss. Chat (oil)	3110	3126		
Miss. Lime	3126	3130		
		T.D.		

KANSAS CORPORATION COMMISSION

JUL 29 2009

RECEIVED

I hereby certify that the foregoing is a true and correct copy of the J. A. Hart #4 well log as recorded on the books of Sun Oil Company, Tulsa, Oklahoma.

*J. H. Allen*

J. H. Allen  
Asst. Prod. Supt.

STATE OF OKLAHOMA) SS  
COUNTY OF TULSA )

Subscribed and sworn to before me this 14th day of May, 1963.

*W. F. Goodner*

Notary Public

My Commission Expires

JUN 28 1964

N E W W E L L  
DRILLING AND COMPLETION PROCEDURES

From: Glen D. Hughes Date: 4-15-63  
To: Mr. R. L. Harris, Yale Office  
Lease: J. A. Hart Well No. 4 County: Cowley, Kansas  
Location: SW SE SE 2-34S-5E  
Location Staked by: County Surveyor Date: \_\_\_\_\_  
Drilling Contractor: Mar-Wik Drlg. Co., Inc., 1124 Douglas Rd., El Dorado, Kan.  
Contract Depth 3150' Maximum Deviation from Vertical: 3 degs.  
Footage Price: \$2.25  
Day Rate: (1) \$540 per 24 hr. day when Contractor's drill pipe in use.  
Day Rate: (2) \$480 per 24 hr. day when Contractor's drill pipe not in use.  
Day Rate: (3) \$288 per 24 hr. day when rig idle at Sun's request.

CASING PROGRAM

<u>Size</u>	<u>Kind &amp; Weight</u>	<u>Amount</u>	<u>To be Obtained From:</u>	<u>Sax Cement</u>
<u>8-5/8"</u>	<u>J55 24#</u>	<u>200'</u>	<u>Whse. (Laverne)</u>	<u>175</u>
<u>4 1/2"</u>	<u>J55 9.5#</u>	<u>3150'</u>	<u>Purchase</u>	<u>125</u>
<u>2-3/8"</u>	<u>H40 4.7#</u>	<u>3150'</u>	<u>Whse. Stock</u>	

KANSAS CORPORATION COMMISSION

JUL 29 2009

RECEIVED

Clearance of Well Site: Sun  
Roadways and Bridges: Sun  
Moving in Material: Contractor  
Cellar and Pits: Contractor  
Fuel: Contractor  
Water: Contractor  
Mud: Sun - Magcobar Mud.

Day Work to Consist of: (1) Circulating for samples  
cc: Messrs. (2) Lost circulation in excess of 24 cumulative hours.  
G. E. Gampbell (3) Coring  
W. R. Gannaway (4) Drill stem or other testing  
J. E. Green (5) Electrical logging  
R. R. Burris (6) All work after oil string set and cemented  
H. A. Logan (7) \_\_\_\_\_  
R. D. Fronterhouse



CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

W.D. SHORT OIL CO., LLC  
102 S RIVER RD  
PO BOX 729  
OXFORD, KS 67119-8801

August 03, 2009

Re: HART #4  
API 15-035-02124-00-00  
2-34S-5E, 360 FSL 1090 FEL  
COWLEY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after January 30, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,

Steve Bond  
Production Department Supervisor

District: #2  
3450 N. Rock Road, Suite 601  
Wichita, KS 67226  
(316) 630-4000