

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
March 2009  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 5056  
Name: F.G. Holl Company, L.L.C.  
Address 1: 9431 E. Central, Suite 100  
Address 2: \_\_\_\_\_  
City: Wichita State: KS Zip: 67206 + \_\_\_\_\_  
Contact Person: Franklin R. Greenbaum  
Phone: (316) 684-8481, Ext. 206

API No. 15 - 047-21,142-0000  
If pre 1967, supply original completion date: \_\_\_\_\_  
Spot Description: \_\_\_\_\_  
NE NW, NE Sec. 4 Twp. 24 S. R. 17  East  West  
4,950 Feet from  North /  South Line of Section  
1,650 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Edwards  
Lease Name: DAVIS Well #: 2-4

Check One:  Oil Well  Gas Well  OG  D&A  Cathodic  Water Supply Well  Other: \_\_\_\_\_  
 SWD Permit #: \_\_\_\_\_  ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks  
Surface Casing Size: 8-5/8" Set at: 261' Cemented with: 210sx Sacks  
Production Casing Size: 4-1/2" Set at: 4427' Cemented with: 225sx Sacks

List (ALL) Perforations and Bridge Plug Sets:

Elevation: 2118' ( G.L. /  K.B.) T.D.: 4435' PBDT: None Anhydrite Depth: 1137'  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Junk in Hole  Casing Leak at: \_\_\_\_\_  
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

**Heavy mud, hulls, cement and plug according to KCC specifications.**

Is Well Log attached to this application?  Yes  No Is ACO-1 filed?  Yes  No

If ACO-1 not filed, explain why:

KANSAS CORPORATION COMMISSION  
**AUG 05 2009**  
**RECEIVED**

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Mr. Rob Long  
Address: 701 E. Santa Fe, Box 308 City: Ellinwood State: KS Zip: 67526 + \_\_\_\_\_  
Phone: (620) 793-0915  
Plugging Contractor License #: 31925 Name: Quality Well Service  
Address 1: 190 US Highway 56 Address 2: \_\_\_\_\_  
City: Ellinwood State: KS Zip: 67526 + \_\_\_\_\_  
Phone: (620) 620-727-3410

Proposed Date of Plugging (if known): Not known

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 8/4/2009 Authorized Operator / Agent: Loveless Company  
(Signature)

*Dist 1  
PKT*

# STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - DAVIS #2-4  
Located: NE NW NE, Section 4-24S-17W, Edwards County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: December 16, 1983

COMPLETED: December 23, 1983

TOTAL DEPTH: 4435'

## LOG

0 - 100 Surface Soil and Sand  
100 - 264 Shale  
264 - 930 Shale, Sand, Red Bed  
930 - 1137 Shale and Red Beds  
1137 - 1150 Anhydrite  
1150 - 1950 Shale  
1950 - 4300 Lime and Shale  
4300 - 4340 Conglomerate Miss.  
4340 - 4435 Lime and Shale

## CASING RECORD

Ran 6 joints new 8 5/8", 24# casing.  
248.73' set at 261' K.B. Cemented  
with 210 sacks 60/40 Poamix, plus  
3% cc. Plug down at 6:15 PM, 12-16-83,  
by Howco.

Ran 117 joints 4 1/2", 10.5# casing.  
(39 joints used) 4418.03' pipe set  
at 4427' K.B. Cemented with 100 sacks  
Lite and 125 sacks 50/50 Pozmix, plus  
our regular additives. Plugged rathole.  
Plug down at 9:55 AM, 12-23-83, by  
Howco.

KANSAS CORPORATION COMMISSION

AUG 05 2009

RECEIVED

Deviation Surveys: 1° at 2238'  
1 1/2° at 4340'



CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

HOLL, F.G., COMPANY L.L.C.  
9431 E CENTRAL STE 100  
WICHITA, KS 67206-2563

August 10, 2009

Re: DAVIS #2-4  
API 15-047-21142-00-00  
4-24S-17W, 330 FNL 1650 FEL  
EDWARDS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after February 6, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,

Steve Bond  
Production Department Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888