

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
March 2009
This Form must be Typed
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5056
Name: F.G. Holl Company, L.L.C.
Address 1: 9431 E. Central, Suite 100
Address 2: _____
City: Wichita State: KS Zip: 67206 + _____
Contact Person: Franklin R. Greenbaum
Phone: (316) 684-8481, Ext. 206

API No. 15 - 185-22,907 - 00-01
If pre 1967, supply original completion date: _____
Spot Description: _____
C - NE NW Sec. 19 Twp. 24 S. R. 15 East West
660 Feet from North / South Line of Section
3,300 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Stafford
Lease Name: YOUNG owwo Well #: 2-19

Check One: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: _____
 SWD Permit #: _____ ENHR Permit #: _____ Gas Storage Permit #: _____
Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8-5/8" Set at: 381' Cemented with: 250sx Sacks
Production Casing Size: 4-1/2" Set at: 4523' Cemented with: 225sx Sacks

List (ALL) Perforations and Bridge Plug Sets:

Elevation: 2058' (G.L. / K.B.) T.D.: 4525' PBDT: 4502' Anhydrite Depth: 1017'
(Stone Corral Formation)

Condition of Well: Good Poor Junk in Hole Casing Leak at: _____
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

Heavy mud, hulls, cement and plug according to KCC specifications.

Is Well Log attached to this application? Yes No Is ACO-1 filed? Yes No

If ACO-1 not filed, explain why:

KANSAS CORPORATION COMMISSION

AUG 05 2009
RECEIVED

Plugging of this Well will be done in accordance with K.S.A. 55-101 et seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Mr. Rob Long
Address: 701 E. Santa Fe, Box 308 City: Ellinwood State: KS Zip: 67526 + _____
Phone: (620) 793-0915
Plugging Contractor License #: 31925 Name: Quality Well Service
Address 1: 190 US Highway 56 Address 2: _____
City: Ellinwood State: KS Zip: 67526 + _____
Phone: (620) 620-727-3410

Proposed Date of Plugging (if known): Not known

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 8/4/2009 Authorized Operator / Agent: Loueness Mearje
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT

STERLING DRILLING COMPANY

1

BOX 129

STERLING, KANSAS 67579

June 9, 1993

SAMPLE LOG-----Young #2-19
Located C-NE-NW, Sec.19,T24S-R15W,Stafford Co., Ks.

OWNER: F.G. Holl Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: May 31, 1993

COMPLETED: June 8, 1993

TOTAL DEPTH: 4525' K.B. Driller
4525' K.B. Logger

LOG

0'-100'	Surface Soil & Sand
100'-385'	Red Bed
385'-495'	Red Bed
495'-1019'	Shale
1019'-1036'	Anhydrite
1036'-4525'	Lime & Shale

CASING RECORD

Spud at 7:00 a.m., 5-31-93
Drilled 385' of 12 1/4" hole
Ran 10 joints of 8 5/8" 24#
New Casing 368.44' pipe set
at 381' K.B. cemented with
250 sacks of 60x40 pozmix
with 2% gel & 3% CC, Plug
down at 1:00 p.m. 5-31-93
by Allied Cementing Co., with
Good returns to surface.

DEVIATION SURVEYS

3/4	at	385'
1/2	at	3802'
3/4	at	4525'

Ran 110 joints of 4 1/2" 10.5#
New & Used casing (560.83' was
used, F.G. Holl Stock, SDC
Yd) 4514.63' pipe set at 4523'
K.B. cemented with 20 BBL Salt
Flush, & 500 Gal. of Superflush
ahead of 100 sacks of Lite
cement, followed with 125 sacks
of F.G. Holl mix. Plug down
at 3:45 p.m. 6-8-93 by H.O.W.C.O
Centralizers on joints 1-8-15-
21 & 33. Shoe joint was 9.85'
long. Plugged rathole with
15 sacks.

KANSAS CORPORATION COMMISSION

AUG 05 2009

RECEIVED



CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

HOLL, F.G., COMPANY L.L.C.
9431 E CENTRAL STE 100
WICHITA, KS 67206-2563

August 10, 2009

Re: YOUNG OWWO #2-19
API 15-185-22907-00-01
19-24S-15W, 660 FNL 3300 FEL
STAFFORD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after February 6, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888