

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
March 2009
**This Form must be Typed
Form must be Signed
All blanks must be Filled**

OPERATOR: License #: 5123
Name: Pickrell Drilling Company, Inc.
Address 1: 100 S. Main
Address 2: Suite 505
City: Wichita State: KS Zip: 67202 +
Contact Person: Jack Gurley
Phone: (316) 262-8427

API No. 15 - 007-23337 - 0000
If pre 1967, supply original completion date: _____
Spot Description: _____
nwne Sec. 4 Twp. 30 S. R. 15 East West
560 Feet from North / South Line of Section
2,150 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Barber
Lease Name: Lee "F" Well #: 2

**KANSAS CORPORATION COMMISSION
AUG 07 2009
RECEIVED**

Check One: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: _____
 SWD Permit #: _____ ENHR Permit #: _____ Gas Storage Permit #: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8 5/8 Set at: 262 Cemented with: 450 60/40 Pozplus 400 sx down outside of csg. Sacks
Production Casing Size: 5 1/2 Set at: 4724 Cemented with: 150 Sacks

List (ALL) Perforations and Bridge Plug Sets:

Perforations 4610-4614 (Viola)

Elevation: 1948 (G.L. / K.B.) T.D.: 4850 Arb PBTD: 4698 ~~Anhydrite~~ Depth: Heebner Sh. 3836 (-1888)
(Stone Corral Formation)

Condition of Well: Good Poor Junk in Hole Casing Leak at: _____
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

Plug back w/ sand from PBTD to 4550. Use dump bailer to spot 5 sx. of cement on top of sand. Cut and free up casing. Pull casing from hole spotting cement plugs as required by K.C.C. Representative as pulled from hole. Refill hole from surface when all casing pulled.

Is Well Log attached to this application? Yes No Is ACO-1 filed? Yes No

If ACO-1 not filed, explain why:

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Deon Howard
Address: 2485 S. State Rd. 14 City: Kingman State: KS Zip: 67068 + 8629
Phone: (620) 793-2316 (cell)
Plugging Contractor License #: 31925 Name: Quality Well Service
Address 1: 190 U.S. 56 Hwy Address 2: _____
City: Ellinwood State: KS Zip: 67526 +
Phone: (620) 938-2388 or 620-727-3410 cell or 620-727-3409 cell

Proposed Date of Plugging (if known): Unknown

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 08-06-09 Authorized Operator / Agent: Jack Gurley (Signature)

Dust / PPT

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

PICKRELL DRILLING COMPANY, INC.
100 S MAIN STE 505
WICHITA, KS 67202-3738

August 11, 2009

Re: Lee "F" #2
API 15-007-23337-00-00
4-30S-15W, 560 FNL 2150 FEL
BARBER COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after February 7, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888