

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-24080-00-00  
Spot: NWSWSE Sec/Twnshp/Rge: 12-18S-21W  
800 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: YOUNG Well #: 1-12  
County: NESS Total Vertical Depth: 2284 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	227		WITH 150 SX CMT
PROD	4.5	2283	0	WITH 275 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/14/2009 10:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (785) 398-2270

Proposed Plugging Method: FILL CASING WITH HULLS & CMT. CHECK BACKSIDE.  
74.23

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/14/2009 12:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMP 200# HULLS & 150 SX CMT. MAXIMUM PRESSURE 150#. SHUT IN PRESSURE 0#. TIED ONTO BACKSIDE & PUMPED 25 SX CMT. PRESSURED TO 500# & HELD. WAITED 1 1/2 HOURS & TOPPED OFF WITH 60 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2236	2240		
2180	2186		

INVOICED  
DATE 8-7-09  
INV. NO. 2010060065

RECEIVED  
JUN 12 2009  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed Michael Maier  
(TECHNICIAN)

RECEIVED  
MAY 27 2009  
KCC DODGE CITY

Form CP-23

PKT