

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21410-00-01
Spot: NESWSW Sec/Twnshp/Rge: 20-33S-33W
1258 feet from S Section Line, 3988 feet from E Section Line
Lease Name: THOMPSON F Well #: 1H
County: SEWARD Total Vertical Depth: 3031 feet

Operator License No.: 4549
Op Name: ANADARKO PETROLEUM CORPORATI
Address: PO BOX 1330
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	660		WITH 510 SX CMT
PROD	5.5	3030	709	WITH 310 SX CMT

Well Type: SWD UIC Docket No: D27789.0 Date/Time to Plug: 06/03/2009 12:30 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 500# HULLS & 25 SX CMT ON BOTTOM. PLUG AT 1600' WITH 50 SX CMT. PLUG AT 690' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.
98.51

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/03/2009 3:00 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

PUMP 500# HULLS & 25 SX CMT AT 2614'. 1ST PLUG AT 1600' WITH 25 SX CMT. 2ND PLUG SHOT PIPE @ 709' & PULLED TO 665'. PUMPED MUD TO SURFACE THEN 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2915	2946		
2614	2682		

INVOICED
DATE 8-7-09
INV NO. 2010060066

RECEIVED
JUN 15 2009
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01

Signed

Jerry W. Stapleton
PIRITI

(TECHNICIAN)

RECEIVED
JUN - 9 2009
KCC DODGE CITY