

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-00463-00-00
Spot: S2 Sec/Twnshp/Rge: 9-30S-32W
1250 feet from S Section Line, 1250 feet from E Section Line
Lease Name: ELLIOT B Well #: 1
County: HASKELL Total Vertical Depth: 2763 feet

Operator License No.: 5952
Op Name: BP AMERICA PRODUCTION COMPANY
Address: 2225 W OKLAHOMA AVE
ULYSSES, KS 67880

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	674		WITH 400 SX CMT
PROD	5.5	2729	0	WITH 900 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/14/2009 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: FILL CASING WITH CMT TOP TO BOTTOM. CHECK BACKSIDE.

89.80

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/14/2009 12:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

PUMP 150# HULLS & 50 SX CMT AT 2654'. TAGGED TOC @ 2155'. RIH W/ TBG TO 2130'. PUMPED 200# HULLS & 170 SX CMT. FILLED TO SURFACE. PUMPED 10 SX CMT DOWN 5 1/2" ANNULUS. PRESSURED TO 400 PSI.

Perfs:

Top	Bot	Thru	Comments
2729	2763		OH
2654	2713		

RECEIVED
JUN 12 2009
KCC WICHITA

INVOICED
DATE: 8-7-09
INV. NO. 2010060068

Remarks: USED 60/40 POZMIX 4% GEL BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed Jack MacLaskey
(TECHNICIAN)

RECEIVED

MAY 20 2009

KCC DODGE CITY

Form C-772

PKT