

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-10154-00-02
Spot: NWSENE Sec/Twnshp/Rge: 33-29S-33W
3311 feet from S Section Line, 762 feet from E Section Line
Lease Name: WALTER E. PREEDY 'B' Well #: 2
County: HASKELL Total Vertical Depth: 4714 feet

Operator License No.: 5952
Op Name: BP AMERICA PRODUCTION COMPANY
Address: 2225 W OKLAHOMA AVE
ULYSSES, KS 67880

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		800		WITH 2 SX CMT
SURF	8.625	754		WITH 650 SX CMT
L1	2.875	4025	808	CMT TO SURFACE FELL BACK TOC @ 1170
PROD	5.5	4714	0	WITH 200 SX CMT

Well Type: SWD UIC Docket No: D23835.0 Date/Time to Plug: 05/12/2009 8:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

153.21

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/12/2009 4:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

PUMP 100# HULLS & 25 SX CMT IN PERF @ 4218'. CIBP @ 800' WITH 2 SX CMT.
PUMP 80 SX CMT FROM 760' TO SURFACE. PUMP 2 SX CMT DOWN 5 1/2" X 8 5/8"
ANNULUS. PRESSURE TO 500 PSI. RAN CMT BOND LOG FROM 800' TO SURFACE.
INDICATED GOOD CMT BOND FROM 200' TO SURFACE, QUESTIONABLE FROM 800'
TO 200'. PERFORATE 5 1/2" @ 761'. COULDN'T PUMP INTO @ 800 PSI.

Perfs:

Top	Bot	Thru	Comments
4664	4677		
4360	4360		
4218	4224		

RECEIVED

JUN 12 2009

KCC WICHITA

INVOICED

DATE: 8-7-09

INV. NO. 2010060068

Remarks: USED 60/40 POZMIX 4% GEL BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED

MAY 20 2009

KCC DODGE CITY

Signed

Jack MacLuskey
(TECHNICIAN)

PKT