

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-20642-00-00  
Spot: NWSEWSW Sec/Twnshp/Rge: 9-29S-6W  
492 feet from S Section Line, 4615 feet from E Section Line  
Lease Name: KLAVER Well #: 2  
County: KINGMAN Total Vertical Depth: 4112 feet

Operator License No.: 5348  
Op Name: CAMPBELL, ROBERT E.  
Address: 260 N ROCK RD STE 110  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP	4.5	3360		
SURF	8.625	259		225 SXS CMT
PROD	4.5	4100	2575	325 SXS CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/27/2009 10:00 AM  
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION  
Proposal Revd. from: THAD STARR Company: AMERICAN ENERGIES CORP Phone: (316) 263-5785

Proposed Plugging Method: SAND TO 3230 AND 4 SKS RECOVER PIPE. 35 SKS 950', 35 SKS 550', CIRC CMT 300-0'.  
133.64

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 05/27/2009 12:30 PM KCC Agent: STEVE VANGIESON

**Actual Plugging Report:**

THE PERFS WERE COVERED WITH SAND TO 3080', AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 2575' AND PULLED TO 952', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 571', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 285', WHERE CMT WAS CIRC TO SURFACE.

**Perfs:**


Top	Bot	Thru	Comments
3279	3282	CSG	

RECEIVED  
JUN 12 2009  
KCC WICHITA

INVOICED  
DATE: 8-7-09  
INV. NO. 2010060070

Remarks: ALLIED CMTG COMMON 3% CACL  
Plugged through: CSG

District: 02

Signed   
(TECHNICIAN)

JK

PKT