

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20945-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 23-32S-26W
1800 feet from S Section Line, 330 feet from W Section Line
Lease Name: FLO Well #: 23-1
County: MEADE Total Vertical Depth: 5650 feet

Operator License No.: 5278
Op Name: EOG RESOURCES, INC.
Address: 3817 NW EXPRESSWAY STE 500
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5405		WITH 2 SX CMT
SURF	8.625	917		WITH 425 SX CMT
PROD	4.5	5650	1984	WITH 200 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/12/2009 9:50 AM

Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.

Proposal Rcvd. from: CANDY DRISCOLL Company: EOG RESOURCES Phone: (405) 246-3100

Proposed Plugging Method: CIBP @ 5405' IWHT 2 SX CMT. PLUG AT 1017' IWHT 100 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 34' WITH 10 SX CMT.

183.63

Plugging Proposal Received By: STEVE DURRANT
Date/Time Plugging Completed: 06/12/2009 10:05 AM

WitnessType: COMPLETE (100%)
KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

CIBP @ 5405' WITH 2 SX CMT. 1ST PLUG AT 1017' WITH 100 SX CMT. SDFW.
6/15/09: TAG TOC @ 803'. 2ND PLUG PULLED TBG TO 400' & PUMPED 50 SX CMT.
3RD PLUG AT 60' WITH 15 SX CMT. CMT CIRCULATED.

INVOICED
DATE 8-7-09
INV. NO. 2010060077

Remarks: USED 60/40 POZMIX 4% GEL BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
JUN 16 2009
KCC DODGE CITY

RECEIVED
JUN 22 2009
KCC WICHITA

PKT