

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21682-00-00
Spot: N2SESW Sec/Twnshp/Rge: 9-10S-17W
990 feet from S Section Line, 3300 feet from E Section Line
Lease Name: FRITTY Well #: 2
County: ROOKS Total Vertical Depth: 3690 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 S ST FRANCIS PO BOX 2757
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	257	0	w/150 sxs cmt
PROD	4.5	3687	0	w/225 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/29/2009 9:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY Phone: (785) 259-1928

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.
Top of cement 2455'.
Squeezes at 996' w/250 sxs; 1038'-1045' w/200 sxs.
119.93

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/29/2009 11:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2444' - pumped 160 sxs 60/40 pozmix - 4% gel with 300# hulls - circulated cement to surface.
Pulled all tubing. Hooked on 4 1/2" casing - pumped 105 sxs 60/40 pozmix - 4% gel with 150# hulls.
S.I.P. 500#.
Hooked onto 8 5/8" - pumped 10 sxs 60/40 pozmix - 4% gel.
S.I.P. 350#.

Perfs:

Top	Bot	Thru	Comments
3552	3558		
3542	3547		

INVOICED

DATE: 8-7-09
INV NO. 2010060079

Remarks: ALLIED CEMENTING COMPANY-TICKET #37471.

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

RECEIVED

Form CP-2/3

JUN 05 2009

KCC WICHITA

JUN 02 2009

Pkt


REPLACEMENT CARD

HORIZON PETROLEUM CORPORATION
 833 N. WACO #2 FRITTS 9-10-17W
 WICHITA, KS 67203 C N/2 SE SW

CONTR DUKE DRILLING CO. CTY ROOKS

GEOL _____ FIELD PLAINVILLE

ELV 2079 KB SPD 5/10/82 CARD ISSUED 5/12/83 IP P 70 BO & 30 BWPD
2075 GL CONG 3542-3558 OA



SMP	Tops	Depth/Datum	API 15-163-21,682
TOP	3002- 923	8 5/8 " 257 / 150SX, 4 1/2 " 3687 / 225SX
HEEB SH	3231-1152	DST (1) 3360-3395 (LANS) / 30-30-30-30, (1ST OP) WB IN 9",
TOR	3272-1193	FLUSHED TOOL, (2ND OP), NB, REC 10' DM, SIP 1194-721#, FP
MARM LM	3527-1448	59-69#
CONG	3540-1461	DST (2) 3537-3562 (CONG) / 45-30-45-30, SB THRU-OUT, REC
SIMP SH	3604-1525	370' OIL, 310' MDY OIL, 600' MDY WTRY OIL, 225' W, SIP 632-
SIMP SD	3614-1535	662#, FP 424-632#
ARB	3646-1567	MICT -CO, PF (CONG) 3552-3558, 3542-3547, W / 2 SPF, SWB
RTD	3690-1611	DWN, NAT, GSO, R&T, POP, P 70 BO & 30 BWPD, (GR 31.6°), 6/ 15/82

INFO RELEASED: 2/28/85 - WAS OIL WELL - TIGHT HOLE