

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-00711-00-00
Spot: NESESE Sec/Twnshp/Rge: 10-22S-14W
1009 feet from S Section Line, 334 feet from E Section Line
Lease Name: P OMLOR Well #: 1
County: STAFFORD Total Vertical Depth: 3825 feet

Operator License No.: 7383
Op Name: GRADY BOLDING CORPORATION
Address: PO BOX 486
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3580		
SURF	8.625	323		WITH 250 SX CMT
PROD	5.5	3677	2010	WITH 125 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/28/2009 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 3500' WITH 5 SX CMT. PLUG AT 840' WITH 12 SX GEL & 50 SX CMT. PLUG AT 350' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.
124.31

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/28/2009 1:15 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3490' & 5 SX CMT. WELL TRYING TO FLOW OIL & GAS. 1872' PUMPED 12 SX GEL TO KILL FLOW. 1ST PLUG AT 840' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 350' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3594	3599		
3550	3559		

INVOICED
DATE: 8-7-09
INV. NO. 2010060080

RECEIVED
JUN 12 2009
KCC WICHITA

Remarks: USED 60/40POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 01

RECEIVED
MAY 29 2009
KCC DODGE CITY

Signed Richard W. Lacey
(TECHNICIAN)

[Handwritten Signature]
PCT