

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-02564-00-00

Spot: SWNWNW

Sec/Twnshp/Rge: 24-26S-18E

4257 feet from S Section Line, 4852 feet from E Section Line

Lease Name: WEINER

Well #: KK 23

County: ALLEN

Total Vertical Depth: 400 feet

Operator License No.: 101 Fec Fund

Op Name: KANSAS CORPORATION COMMISSION

Address: 130 S MARKET RM 2078
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10	20	0	
PROD	2	400	0	

Well Type: EOR

UIC Docket No: E00591.100

Date/Time to Plug: 03/27/2009 8:00 AM

Plug Co. License No.: 3097

Plug Co. Name: K W OIL WELL SERVICE. INC.

Proposal Rcvd. from: STATE FEE FUND

Company: KCC

Phone: (316) 337-6200

Proposed Plugging Method: Clean out and prepare well for plugging. Run cement string to TD and circulate cement to surface.

Plugging Proposal Received By: RYAN DULING

WitnessType: NONE

Date/Time Plugging Completed: 03/27/2009 5:00 PM

KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Used pulling unit and left hand out 1" to 400'. Ran 1" to 400' inside 2" production pipe. Ran 1" to 375' outside of 2" production pipe. Washed down to 450'. Circulated cement inside and outside 2" production pipe to surface. Pulled both cement strings and topped off. A total of 182 sacks of portland cement was used to plug this well. The well was cut off below grade and the location was restored.

RECEIVED
KCC DISTRICT #3

APR 29 2009

RMB

CHANUTE, KS

KANSAS CORPORATION COMMISSION

MAY 04 2009

RECEIVED

Remarks: CONTROL # 20090013-017 GPS #WIT17

Plugged through: CSG

District: 03

Signed

[Signature]

(TECHNICIAN)