

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-019-19610-00-01  
Spot: SENE Sec/Twnshp/Rge: 31-32S-11E  
2970 feet from S Section Line, 990 feet from E Section Line  
Lease Name: FLOYD B Well #: 2  
County: CHAUTAUQUA Total Vertical Depth: 2096 feet

Operator License No.: 33866  
Op Name: MARIAH EXPLORATION LLC  
Address: 29611 W US HWY 60 PO BOX 1452  
PAWHUSKA, OK 74056

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	75		
T1	2.375	1876		
PKR		1876		
PROD	5.5	2095		

68.12

Well Type: EOR UIC Docket No: E20902.1 Date/Time to Plug: 06/03/2009 2:00 PM

Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: 50' plug at 1895', 50 plug at 950' and 350' to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/04/2009 10:30 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 1880' gelled hole and spotted 12 sack plug. Pulled 1" up to 950' and spotted another 12 sack plug. Pulled 1" up to 350' and circulated cement to surface. Pulled 1" and topped well off. Contractor had to come back next day and top well off again. A total of 70 sacks of cement were used to plug this well.

RECEIVED  
KCC DISTRICT #3

JUN 16 2009

DAS

CHANUTE, KS

INVOICED  
DATE: 8-12-09  
INV. NO. 2010060088

KANSAS CORPORATION COMMISSION

JUN 19 2009


RECEIVED

Remarks: PIPE WAS SHOT OFF OF PACKER AND PACKER DROVE TO BOTTOM OF WELL.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

PKR