

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-24609-00-00
Spot: NESESW Sec/Twnshp/Rge: 8-33S-11E
990 feet from S Section Line, 2970 feet from E Section Line
Lease Name: FLOYD RANCH Well #: 9 36
County: CHAUTAUQUA Total Vertical Depth: 2373 feet

Operator License No.: 33866
Op Name: MARIAH EXPLORATION LLC
Address: 29611 W US HWY 60 PO BOX 1452
PAWHUSKA, OK 74056

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF		41		

77.12

Well Type: SWD UIC Docket No: D27400.0 Date/Time to Plug: 06/04/2009 1:00 PM

Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 50' plug at 2373, 50' plug at 900' and 350' to surface.

Plugging Proposal Received By: DUANE SIMS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 06/05/2009 10:00 AM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Operator shot pipe off of packer which was set at 950' and pulled pipe. Contractor ran 1" through packer and hit something solid at 1320'. Contractor gelled hole and spotted 10 sack plug. Pulled up to 900' and spotted another 10 sack plug. Pulled 1" to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 55 sacks of cement were used to plug this well.

INVOICED
DATE 8-12-09
INV. NO. 2010060088

RECEIVED
KCC DISTRICT #3

JUN 16 2009

CHANUTE, KS

DAS

KANSAS CORPORATION COMMISSION

JUN 19 2009

RECEIVED

Remarks: PACKER WAS LEFT IN WELL AND SOME PIPE IN BOTTOM OF WELL.

Plugged through: TBG

District: 03

Signed

Duane Sims

(TECHNICIAN)