

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24621-00-00
Spot: SWSENE Sec/Twnshp/Rge: 10-20S-12W
2970 feet from S Section Line, 865 feet from E Section Line
Lease Name: DOONAN Well #: 1
County: BARTON Total Vertical Depth: 3376 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	305	0	195 SX
PROD	5.5	3360	1683	140 SX

109.72

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/02/2009 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMLAN Company: L.D. DRILLING, INC. Phone: (620) 793-3051

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/02/2009 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Cut casing at 1683' - pulled to 1503'.
Tied to casing - pumped 150 sxs cement with 300# hulls.
Pulled to 600' - pumped 60 sxs cement with 100# hulls.
Pulled to 200' - pumped 120 sxs cement - circulated to surface.
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3360	3376		

INVOICED
DATE 8-12-09
INV. NO. 2010060083

RECEIVED
JUN 18 2009
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #35344.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

LM

Form CP-2/3

JUN 12 2009

PKT

replacement card

LD DRILLING
GREAT BEND KS 67530

10-20S-12W
125'E, C SW SE NE

1 DOONAN

site: 1-1/4 S & 2 W OF ELLINWOOD KS
contr: LD DRILLING # 1

ty: BARTON
field: HOOD

API 15-009-24621

well:
fr date 01/31/97 spd date 03/06/97 drlg comp 03/21/97 card issued 07/21/97 last revised 09/29/97

ELV: 1806 KB, 1801 GL SMP

tops.....	depth/datum
ANH.....	590 + 1216
B/ANH.....	610 + 1196
HEEB.....	2981 -1175
TOR.....	3001 -1195
DOUG.....	3015 -1209
BR LM.....	3101 -1295
LANS.....	3117 -1311
BKC.....	3351 -1545
ARB.....	3357 -1551
RTD.....	3376 -1570
NO LOG	

IP status:
OIL, P 10 BOPD, ARB 3360-3376 , 03/ 28/ 97
INFO RELEASED: 9/29/97 - WAS OIL WELL - TIGHT HOLE
CSG. 8-5/8" 305 / 195 SX (ALT 1), 5-1/2" 3360 / 140 SX
COMMENT: RIG SHUTDOWN FOR TIME FOR REPAIRS AT 3200 - RESUMED DRLG 3/13/97
NO CORES
DST (1) 3130-3200 (LANS B-F), / 30-30-30-30, REC 25' SLI
OCM 1SIP 89# FSIP 69# IFP 56# -58# FFP 47# -56#
DST (2) 3252-3330 (LANS H-K), / 30-30-30-30, 95' GIP,
REC 30' SLI OIL & GCWM (5% OIL), 47' SLI GCMW, 62' GCMW 1SIP 758# FSIP 647# IFP 78# -123# FFP 89# -127#

COPYRIGHT 1997
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)