

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 12 2006

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

ORIGINAL

Form ACO-1
September 1999
Form Must Be Typed

CONSERVATION DIVISION
WICHITA, KS

WELL COMPLETION FORM

WELL HISTORY - DESCRIPTION OF WELL & LEASE

Operator: License # 31609
 Name: Priority Oil & Gas LLC
 Address: PO Box 27798
 City/State/Zip: Denver, CO 80227-0798
 Purchaser: Enserco Energy
 Operator Contact Person: Robbie Gries
 Phone: (303) 296-3435
 Contractor: Name: Advanced Drilling Technologies
 License: 33532
 Wellsite Geologist: none
 Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)
 If Workover/Re-entry: Old Well Info as follows:
 Operator: _____
 Well Name: _____
 Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back _____ Plug Back Total Depth
 Commingled Docket No. _____
 Dual Completion Docket No. _____
 Other (SWD or Enhr.?) Docket No. _____

<u>02-28-06</u>	<u>03-1-06</u>	<u>3/13/06</u>
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 023-20656-00-00
 County: Cheyenne
w/2 SE SE SE Sec. 29 Twp. 3 S. R. 41 East West
330 feet from (S) N (circle one) Line of Section
490 feet from (E) W (circle one) Line of Section
 Footages Calculated from Nearest Outside Section Corner:
 (circle one) NE (SE) NW SW
 Lease Name: Schlepp Well #: 3-29
 Field Name: Cherry Creek
 Producing Formation: Beecher Island/Niobrara
 Elevation: Ground: 3624' Kelly Bushing: 3636'
 Total Depth: 1610' Plug Back Total Depth: 1581'
 Amount of Surface Pipe Set and Cemented at 311' @ 324' KB Feet
 Multiple Stage Cementing Collar Used? Yes No
 If yes, show depth set _____ Feet
 If Alternate II completion, cement circulated from N/A
 feet depth to _____ w/ _____ sx cmt.

Drilling Fluid Management Plan AIT I NR
 (Data must be collected from the Reserve Pit) 11-3-08
 Chloride content ~18-19,000 ppm Fluid volume ~250 bbls
 Dewatering method used Evaporate
 Location of fluid disposal if hauled offsite: _____
 Operator Name: _____
 Lease Name: _____ License No.: _____
 Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
 County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Robbie Gries
 Title: President Date: 5-10-06
 Subscribed and sworn to before me this 10th day of May,
2006
 Notary Public: [Signature]
 Date Commission Expires: 3/29/09

KCC Office Use ONLY

Letter of Confidentiality Attached
 If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution

Operator Name: Priority Oil & Gas LLC Lease Name: Schlepp Well #: 3-29
 Sec. 29 Twp. 3 S. R. 41 East West County: Cheyenne

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken Yes No
 (Attach Additional Sheets)
 Samples Sent to Geological Survey Yes No
 Cores Taken Yes No
 Electric Log Run Yes No
 (Submit Copy)

Log Formation (Top), Depth and Datum Sample
 Name Top Datum
 Niobrara
 Beecher Island 1432' 2204 mls

List All E. Logs Run:
 CNL-Density
 Induction-SP-GR
 Cement Bond

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 12 2006

CONSERVATION DIVISION
WICHITA, KS

CASING RECORD New Used
 Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (in O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	9 1/2 in	7 in	20 #	324' KB	Portland I/II	78	
Production	6 1/4 in	4 1/2 in	10.5 #	1582'	Type I-II	75	2% kcl

ADDITIONAL CEMENTING / SQUEEZE RECORD

Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone				


Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type		Acid, Fracture, Shot, Cement Squeeze Record	
	Specify Footage of Each Interval Perforated		(Amount and Kind of Material Used)	
4	1434'-1440'		500 gal, 7.5% HCl, CO2 foam frac w/	Depth 1434-
2	1441'-1468'		100,810# 16/30 Brady sand	1468

TUBING RECORD Size none Set At _____ Packer At _____ Liner Run Yes No

Date of First, Resumed Production, SWD or Enhr. _____ Producing Method Flowing Pumping Gas Lift Other (Explain) _____

Estimated Production Per 24 Hours Oil Bbls. none Gas Mcf 77.73 Water Bbls. none Gas-Oil Ratio _____ Gravity _____

Disposition of Gas Vented Sold Used on Lease (If vented, Sumit ACO-18.)
 METHOD OF COMPLETION Open Hole Perf. Dually Comp. Commingled
 Production Interval Other (Specify) _____



A DIVISION OF ADVANCED DRILLING TECHNOLOGIES, LLC.

LONGHORN CEMENTING CO.

P.O. BOX 203 YUMA, COLORADO 80759
 Phone: 970-848-0799 Fax: 970-848-0798

FIELD SERVICE TICKET
AND INVOICE

DATE 3-1-06 TICKET NO. 0509

DATE OF JOB	DISTRICT	NEW WELL <input checked="" type="checkbox"/>	OLD WELL <input type="checkbox"/>	PROD <input type="checkbox"/>	INJ <input type="checkbox"/>	WDW <input type="checkbox"/>	CUSTOMER ORDER NO.:
CUSTOMER	<u>PRIORITY</u>	LEASE	<u>Schlepp 3-29</u>			WELL NO.:	
ADDRESS		COUNTY				STATE	
CITY	STATE	SERVICE CREW	<u>MIKKE</u>				
AUTHORIZED BY		EQUIPMENT	<u>UNIT #11</u>				
TYPE JOB: <u>CONCRETE</u>	DEPTH FT.	CEMENT DATA: BULK <input type="checkbox"/>	SAND DATA: SACKS <input type="checkbox"/>	TRUCK CALLED		DATE	AM
SIZE HOLE:	DEPTH FT.	SACKS	BRAND	TYPE	% GEL	ADMIXES	PM
SIZE & WT. CASTING	DEPTH FT.	<u>75</u>		<u>1-11</u>			ARRIVED AT JOB
SIZE & WT. D PIPE OR TUBING	DEPTH FT.						START OPERATION
TOP PLUGS	TYPE:	WEIGHT OF SLURRY: <u>14.8</u>	LBS. / GAL. <u>(6.3)</u>	LBS. / GAL.			FINISH OPERATION
		VOLUME OF SLURRY	<u>1.32</u>	<u>CU FT / SLK</u>			RELEASED
		<u>75</u> SACKS CEMENT TREATED WITH <u>2</u> % OF <u>Calcium</u>					MILES FROM STATION TO WELL
	MAX DEPTH <u>1568.16</u> FT.	MAX PRESSURE					

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).
 The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only these terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without written consent or an officer of Advanced Drilling Technologies, LLC.

SIGNED: _____
 (WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM / PRICE REF. NUMBER	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
001-2	Depth Charge - Cement Mixture As per Contract				410.00
300-2	4 1/2" Accuseal Float shoe	1			267.07
300-4	4 1/2" Latchdown Baffle plug	1			226.28
300-6	4 1/2" Centralizers	7			250.88
300-8	4 1/2" Scratchers	7			243.60
300-11	7" Centralizer	1			36.44
400-2	CLAYSTA	2.5 gal			119.12
400-4	KCCS	100 lb			86.52
400-1	Mud Flush	50 lb			87.75
					5356.49
2205	Mud Flush 10.2				
2210	Cement 17.6				
2220	D. displacement 24.9				
2230	Bump plug @ 1800				

RECEIVED
 KANSAS CORPORATION COMMISSION
 MAY 12 2006

CONSERVATION DIVISION
 WICHITA, KS

ACID DATA:			
GALLONS	%	ADDITIVES	
HCL			
HCL			

SUB TOTAL		
SERVICE & EQUIPMENT	% TAX ON \$	
MATERIALS	% TAX ON \$	
TOTAL		

SERVICE REPRESENTATIVE T HANK YOU THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY: Dale Brunson
 FIELD SERVICE ORDER NO. _____ (WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)