

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5663
Name: Hess Oil Company
Address 1: P. O. Box 1009
Address 2: _____
City: McPherson State: KS Zip: 67460 + 1009
Contact Person: Bryan Hess
Phone: (620) 241-4640

Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)
Cherokee Depth to Top: 4139' Bottom: 4144' T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 195-22,335-00-00
Spot Description: 140' S,
E2 SE SW Sec. 16 Twp. 15 S. R. 22 East West
520 Feet from North / South Line of Section
2,310 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Trego
Lease Name: Werth Well #: 1
Date Well Completed: 5-2-2006
The plugging proposal was approved on: _____ (Date)
by: _____ (KCC District Agent's Name)
Plugging Commenced: 5-29-2009
Plugging Completed: 5-29-2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8-5/8"	211'	none
		Production	5-1/2"	4139'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged with 245 sacks 60/40 pozmix, 4% gel, as follows: Pumped down tubing @ 4082' - 50 sx pozmix w/200# hulls, and 15 sacks gel spacer. Pulled tubing to 1950' and pumped 175 sacks pozmix, circulated to surface. Topped w/20 sacks @ 500#. Checked annulus w/500#.

RECEIVED
JUN 12 2009

Plugging Contractor License #: 5663 Name: Hess Oil Company **KCC WICHITA**
Address 1: P. O. Box 1009 Address 2: _____
City: McPherson State: KS Zip: 67460 + 1009
Phone: (620) 241-4640

Name of Party Responsible for Plugging Fees: Hess Oil Company
State of Kansas County, McPherson, ss.
Bryan Hess, Pres. Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: Bryan Hess 6-11-09

ACT

QUALITY OILWELL CEMENTING, INC.

Home Office P.O. Box 32 Russell, KS 67665

No. 3123

Phone 785-483-2025
Call 786-324-1041

Date	5/29/09	Sec.	16	Twp.	15	Range	22	County	Trego	State	KS	On Location		Finish	12:30 PM
Lease	Worth	Well No.		Location				Cedar Bluff Dam. 3 S, 2 W, 10 N, 1/2 W, N 1/4							
Contractor	Fritzer	Owner				To Quality Oilwell Cementing, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.									
Type Job	Plug	Charge To				Hess Oil Company									
Hole Size		T.D.	Street				City				State				
Csg. Size	5 1/2"	Depth	The above was done to satisfaction and supervision of owner agent or contractor.												
Tbg. Size	2 7/8"	Depth	Amount Ordered				15 gal CEMENT 200# Hulls (Used)								
Drill Pipe		Depth	Common				325 sx 60/40 4% gal (245)								
Tool		Depth	Poz. Mix				147 @ 10.00				1470.00				
Cement Left in Csg.		Shoe Joint	Gel.				98 @ 6.00				588.00				
Press Max.		Minimum	Flowseal				24 @ 17.00				408.00				
Meas Line		Displace	Calcium				Hull 2 @ 25.00				50.00				
Perf.			Salt												

EQUIPMENT

Pumptrk	9	No.	Cementor	Paul
Bulktrk	4	No.	Driver	Brian
Bulktrk	PV	No.	Driver	Darin

JOB SERVICES & REMARKS

Pumptrk Charge	PTA	210.00
Mileage	35 @ 6.00	210.00
Footage		
Total		210.00

Handling	351 @ 2.75	614.25
Mileage	87 per 1/2 per mile	500.00
Pump Truck Charge		210.00

Remarks: Plug at 4082' - Mix 15 gal -
Mix 50 sx - 200 # Hulls

FLOAT EQUIPMENT

Plug at 1950' - Mix 175 sx
Circulate Cement

Top Off with 20 sx at 500 #

Back side - 500 #

Guide Shoe		
Centralizer		
Baskets		
AFU Inserts		

RECEIVED
JUN 12 2009
KCC WICHITA

Thank You!!

Rotating Head		
Squeeze Mainfold		
Tax		206.39
20% Discount		(868.00)
Total Charge		3673.59

Signature