

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION**

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**Well Plugging Record
K.A.R. 82-3-117**

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Campbell Oil and Gas Operations
Address: 260 N. Rock Road, Suite 110, Wichita, KS 67206
Phone: (316) 685-6001 Operator License #: 5348
Type of Well: Gas Docket #: _____
(Oil, Gas, D & A, SWD, ENHR, Water supply Well, Cathodic, Other)
The plugging proposal was approved on: 5/21/2009 (Date)
by: Steve VanGieson (KCC District Agent's Name)
Is ACO-1 filed? YES No ACO-1 Attached, as well as logs and DST results
If not, is well log attached? Yes _____ No
Producing Formation(s): List All (if needed attach another sheet)
MISN Depth to 1 Top: 4443 Bottom: 4457 T.D.
VIOLA Depth to 1 Top: 4457 Bottom: 4460 T.D. 4460
Depth to Top: _____ Bottom: T.D.

API # 15-095-21168-0000
Lease Name: Benson-Yeager
Well Number: #2
Spot Loc. (QQQQ): SW NW
460' NW of C.W/2 NW SE
2085 Feet from North South Section Line
2415 Feet from North South Section Line
Sec. Section 9-T29S-R6W East/West
County: Kingman
Date Well Completed: 10/8/1981
Plugging Commenced: 5/18/2009
Plugging Completed: 5/21/2009

KCC REP 675

Show depth and thickness of all water, oil and gas formation:

OIL, GAS OR WATER RECORDS		CASING RECORD (Surface Conductor & Production)				
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface	Water sands	218	0'	8 5/8" 23#	218'	None
Production	Water sands	0	4459'	5 1/2"	4459'	75 JTS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from (bottom), to (top) for each plug set.

5/18/2009 Pump would not unseat, so began stripping. 1st rod break - 27 rods. Pulled rods, then tubing to rods. 2nd rod break - 32 rods. Pulled rods and tubing.

5/19/2009 Completed stripping well. Ran in swab and tagged bottom @ 4286'. Dumped 55 sx sand down casing. Set 2 hours, went in with swab bar and tagged sand @ 4060'. Dumped additional 10 sx sand.

5/20/2009 Tagged sand @ 3900'. Mixed 4 sx cement. Used dump bailer and added cement on top of sand. Rigged over for casing. Rigged up Log Tech. Went in and shot casing @ 2500'. Recovered 75 jts 5 1/2" casing.

5/21/2009 Ran tubing to 965'. Hooked up Allied Cementing and started circulating hole. Mixed 35 sx Class A Cement with 3% CC and set plug @ 965'. Pulled tubing to 552'. Let 1st plug set for 1 hour. Went in with swab bar and tagged cement @ 920'. Mixed additional 35 sx CC and set 2nd plug @ 552'. Pulled tubing to 302'. Cemented 302' to surface with 120 sx (Allied Ticket #34364).

Name of Plugging Contractor: American Energies Corporation License #: 5399
Address 155 North Market, #710 City: Wichita State: Kansas Zip 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Robert Campbell (Operator)

STATE OF KANSAS COUNTY OF: Sedgwick, ss.

Robert Campbell (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Robert Campbell
Robert Campbell, Owner/Operator

(Address) 260 North Rock Road, Suite 110, Wichita, KS 67206

SUBSCRIBED AND SWORN TO me this 9th day of June 2009

Joyce T. Buss Notary Public My Commission Expires: 01/22/12

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



RECEIVED
JUN 10 2009
KCC WICHITA

Handwritten initials

ALLIED CEMENTING CO., LLC.

34364

TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Medicine Lodge

DATE <u>05-21-09</u>	SEC. <u>9</u>	TWP. <u>29S</u>	RANGE <u>6W</u>	CALLED OUT <u>0800 AM</u>	ON LOCATION <u>11:00 AM</u>	JOB START <u>12:00 PM</u>	JOB FINISH <u>2:30 PM</u>
LEASE <u>Benson Property</u>		WELL # <u>2</u>	LOCATION <u>1/4 Belmont Blocktop. SE, 1S, 1/2 E,</u>		COUNTY <u>Wichita</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one)			<u>N/INTO</u>				

CONTRACTOR American Energy

OWNER Bob Campbell

TYPE OF JOB O.H.P

HOLE SIZE 7 7/8 T.D. 968

CASING SIZE 8 5/8 DEPTH 280'

TUBING SIZE 2 3/8 DEPTH 968'

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX 400 MINIMUM 100

MEAS. LINE SHOE JOINT

CEMENT LEFT IN CSG.

PERFS.

DISPLACEMENT 2 Bbls Fresh water

EQUIPMENT

PUMP TRUCK CEMENTER Greg G
414-302 HELPER Greg G

BULK TRUCK
364 DRIVER Michael N.

BULK TRUCK
DRIVER

REMARKS:

968' - 3.5sx + 380cc
552' - 3.5sx + 390cc
280' - 120sx

CEMENT

AMOUNT ORDERED 190 SX Class A, 3 SX CC.;
67 SX Sand

COMMON Class A 190 @ 15.45 2935.50

POZMIX @

GEL @

CHLORIDE 6 @ 58.20 349.20

ASC @

Sand 67 sx @ 13.10 877.70

@

@

@

@

@

@

@

HANDLING 190 @ 2.40 456.00

MILEAGE 190 / 40 4.75 760.00

TOTAL 5378.40

SERVICE

DEPTH OF JOB 968'

PUMP TRUCK CHARGE 900.00

EXTRA FOOTAGE @

MILEAGE 40 @ 7.00 280.00

MANFOLD @

@

@

TOTAL 1180.00

CHARGE TO: Bob Campbell
STREET

PLUG & FLOAT EQUIPMENT

Post-It® Fax Note	7671	Date	<u>6-3-09</u>	# of pages	<u>2</u>
To	<u>Medicine Lodge</u>	From			
Co./Dept.		Co.			
Phone #		Phone #			
Fax #	<u>316-263-1857</u>	Fax #			

RECEIVED
JUN 10 2009
KCC WICHITA

TOTAL

SALES TAX (If Any)

TOTAL CHARGES

DISCOUNT IF PAID IN 30 DAYS

~~_____~~

~~_____~~

PRINTED NAME Thad Starv

SIGNATURE Thad Starv

Thank You

Kingman Lumber

210 N. Spruce
Kingman, KS 67068
Phone 820-532-3831
Fax 820-532-1259
kingmanlumber@yahoo.com

Same ticket
Benson-yeager

KINGMAN LUMBER CO
210 N SPRUCE
KINGMAN, KS 67068
820-532-3831

Benson-yeager

DATE: 05/19/09 TIME: 11:55
MER#: 688762892620 TERM: 0001
S-A-L-E-S D-R-A-F-T

*AEC-Benson
Yeager #2
5092
OSW10481368*

REF: 0003 BCH: 362
CD TYPE: MC
TR TYPE: PR
AMOUNT: \$48.48
CCT: ~~XXXXXXXXXXXX~~492 EXP: **/**
AP: 291547

CARDMEMBER ACKNOWLEDGES RECEIPT OF
GOODS AND/OR SERVICES IN THE AMOUNT OF
THE TOTAL SHOWN HEREON AND AGREES TO
PERFORM THE OBLIGATIONS SET FORTH BY THE
CARDMEMBER'S AGREEMENT WITH THE ISSUER

[Signature]
TOP COPY-MERCHANT BOTTOM COPY-CUSTOMER

INVOICE 177480
DATE : 05/19/09 11:55:15 AM
CLERK : Sue
PD :
SIGN :
CUSTOMER : Cash Sale

Qty	Item	Desc	Unit Price	Extended
-----	------	------	------------	----------

4	PORTLAND	PORTLAND CEMENT TYPE	\$11.40	\$45.60
---	----------	----------------------	---------	---------

SUBTOTAL :	\$45.60
DISCOUNT :	\$0.00
SALESTAX :	\$2.88
SHIPPING :	\$0.00
TOTAL :	\$48.48
CREDIT CARD TENDERED :	\$48.48
CHANGE :	\$0.00

RECEIVED
JUN 10 2009
KCC WICHITA