

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION**

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

**Well Plugging Record
K.A.R. 82-3-117**

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: C Robert E Campbell
Campbell Oil and Gas Operations

Address: 260 North Rock Road, Suite 110, Wichita, KS 67206

Phone: (316) 685-6001 Operator License # 5348

Type of Well: Gas Oil KCC Docket #: _____
(Oil, Gas, D & A, SWD, ENHR, Water supply Well, Cathodic, Other)

The plugging proposal was approved on: 5/27/2009 (Date)

by: Steve VanGieson (KCC District Agent's Name)

Is ACO-1 filed? YES No ACO-1 Attached, as well
as logs and DST results

If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)

B/KC	Depth to 1 Top: <u>3787</u>	Bottom: <u>4097 T.D.</u>
Mississippian	Depth to 1 Top: <u>4097</u>	Bottom: <u>4112 T.D. 4112</u>
	Depth to Top: _____	Bottom: <u>T.D.</u>

API # 15-095-20642 - 0000

Lease Name: Klaver

Well Number: #2

Spot Loc. (QQQQ): nwse
SW SW

492
660 FGL Feet from North South Section Line
660 FWE Feet from North South Section Line
4015

Sec. Section 9-T29S-R6W East/West

County: Kingman

Date Well Completed: 10/6/1977

Plugging Commenced: 5/22/2009

Plugging Completed: 5/27/2009

*KCC PKT Pm
OPS*

Show depth and thickness of all water, oil and gas formation:

OIL, GAS OR WATER RECORDS		CASING RECORD (Surface Conductor & Production)				
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface	Water sands	259	0'	8"	259'	None
Production	Water sands	0	4100'	4 1/2"	4100'	65 jts

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from (bottom), to (top) for each plug set.

5/22/09 Pulled pump, rods and tubing. Spotted with 25 sx sand.

5/26/09 Went in with swab bar and tagged sand @ 3080'. Ran in with Bailor and dumped 4 sx cement on sand. Rigged up Log Tech shot Casing at 2475'. Pulled 65 jts of 4 1/2" 9.5# casing.

5/27/09 Ran tubing to 952'. Hooked up Allied Cementing and ran 35 sx with 3% CC for 1st plug. Ran in swab bar after 1 hour and tagged @ 870'. Mixed 35 sx with 3% CC and spotted 2nd plug @ 571'. Pulled tubing to 234' and circulated cement to surface with 180 sx (Allied Cementing ticket #34365).

Name of Plugging Contractor: American Energies Corporation License #: 5399

Address 155 North Market, #710 City: Wichita State: Kansas Zip 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Robert Campbell (Operator)

STATE OF KANSAS COUNTY OF: Sedgwick, ss.

Robert Campbell (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature)

Robert Campbell, Owner/Operator

(Address)


260 North Rock Road, Suite 110, Wichita, KS 67206

SUBSCRIBED AND SWORN TO me this 9th day of June 2009

Joyce T. Buss
Notary Public

My Commission Expires: 01/23/12

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



RECEIVED
JUN 10 2009
KCC WICHITA

JTB

DATE JOB STARTED 5-22-09
 LEASE: Klauer
 COUNTY Kingman

DATE JOB COMPLETED: 5-27-09
 WELL # 2

Acidizing _____ Frac Well _____ Perforating Well _____
 Squeeze Job _____ Workover _____

WORK PERFORMED:
 (Please circle appropriate job)

Pump Change:
 New: _____ Rebuilt _____ Size of pump _____

Rod Part: Size & Type of Replacement _____
 Rod Break-Number of Jts. Down _____ Kind of Break _____

Tubing Failure:
 Tubing leak-Number of Jts Down _____ Kind of Break _____ Size & Type of Replacement _____
 Replaced with New _____ or Used _____

Plugging Well: Please Complete Information

<u>4</u>	Number of Sacks cement at
<u>35</u>	Number of Sacks cement at
<u>35</u>	Number of Sacks cement at
<u>rest</u>	Number of Sacks cement at
Total Number of Sacks of Cement _____	

<u>3080</u>	feet	Type of Cement used: _____
<u>952</u>	feet	Ticket number: _____
<u>558</u>	feet	Cementing Company: <u>Allica</u>
<u>283</u>	feet	Date Plugging Completed: <u>5-27-09</u>
		State Plugging Agent: <u>B.J.</u>

Description of Work Performed:
22nd Drive to loc. Rigged up. Total w/ 127 3/4" rods Rigged over for 23 1/2' job
TDH w/ 12 Jts Sanded off w/ 27 sack of sand. 7.5 hrs
26th Tagged cement 3080' mixed 4 sacks ran in w/ dump bucket Rigged
over for 4 1/2" casing. Shot casing off @ 2475' TDH w/ 65 Jts
4 1/2" 8.0 hrs.
27th Rigged over for job. Tailled in 952' Got circ spotted 35 sacks TDH
w/ 12 Jts to 558' Tagged cement over br. Spotted 35 sacks. TDH w/ 9 Jts
to 283' w/ 12 lbs. tagged cement cemented to surface. TDH Rigged
down. 5.5 hrs

Joints	Feet	Size	Pulled from Well:					Equipment	Joints Feet Size					Run in Well:							
			2'	4'	6'	8'	10'		2'	4'	6'	8'	10'	2'	4'	6'	8'	10'			
								Packer													
								Anchor													
								Polished Rod													
								Rods													
								Rods													
			2'	4'	6'	8'	10'	Rod Subs					2'	4'	6'	8'	10'				
								Pump													
								Tubing													
			2'	4'	6'	8'	10'	Tubing Subs					2'	4'	6'	8'	10'				
								Barrel													
								Mud Anchor													

Services	Hours	Per Hour	Amount
Unit and Power Tools	<u>21</u>	\$175.00	\$ <u>3675</u>
Road Time - Per hour		\$175.00	\$ _____
Supervisor time	<u>21</u>	\$40.00	\$ <u>840</u>
Material Transfer			\$ _____
Swab Cups			\$ _____

Signed: _____ Date: 5/24/09

Sales Tax _____
 Total Due \$ 4,515

RECEIVED
 JUN 1 2009

ALLIED CEMENTING CO., LLC.

54365

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Medicine Lodge

DATE <u>5-27-09</u>	SEC. <u>9</u>	TWP <u>29S</u>	RANGE <u>14W</u>	CALLED OUT <u>0700 AM</u>	ON LOCATION <u>9:30</u>	JOB START <u>10:00</u>	JOB FINISH <u>11:30</u>
LEASE <u>Klaver</u>		WELL # <u>2</u>	LOCATION <u>148 Belmont Blacktop, S E, Y2S, E/INTO</u>			COUNTY <u>Kingman</u>	STATE <u>KS</u>
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR American Energies

OWNER Bob Campbell

TYPE OF JOB O.W.P.

HOLE SIZE 7 7/8 T.D. 952

CASING SIZE 4 1/2 DEPTH

TUBING SIZE 2 3/8 DEPTH 952

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX 400 MINIMUM 100

MEAS. LINE SHOE JOINT

CEMENT LEFT IN CSG.

PERFS.

DISPLACEMENT 20bls Fresh Water

EQUIPMENT

PUMP TRUCK CEMENTER Gleg G.

352 HELPER Scott P.

BULK TRUCK

363-314 DRIVER Michgel N.

BULK TRUCK

DRIVER

REMARKS:

952' - 355x + 3% CC

571' - 355x + 3% CC

285' - 1805x

CHARGE TO: Bob Campbell

STREET

CITY STATE ZIP

To Allied Cementing Co., LLC.

You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME Thad Starr

SIGNATURE Thad Starr

* Thank You *

CEMENT

AMOUNT ORDERED 2505x Class A, 35x CC, 295x Sand

COMMON 250 @ 15.45 3862.50

POZMIX @

GEL @

CHLORIDE @

ASC @

35x CC @ 58.20 174.60

275x Sand. @ 13.10 353.70

@

@

@

@

@

@

HANDLING 253 @ 2.40 607.20

MILEAGE 263x.10x40 @ 1012.00

TOTAL 6010.00

SERVICE

DEPTH OF JOB 952'

PUMP TRUCK CHARGE 900.00 900.00

EXTRA FOOTAGE @

MILEAGE 40x7.00 @ 2.00 280.00

MANIFOLD @

@

@

TOTAL 1180.00

PLUG & FLOAT EQUIPMENT

~~NONE~~ @

@

@

@

@

TOTAL

SALES TAX (If Any)

TOTAL CHARGES 7190.00

DISCOUNT 719.00 IF PAID IN 30 DAYS

Net \$ 6471.00

RECEIVED

JUN 10 2009

KCC WICHITA

06/05/2009 09:03

6206204435

AMERICAN ENERGIES

PAGE 01/01

Kingman Lumber

210 N. Spruce
Kingman, KS 67068
Phone 620-532-3831
Fax 620-532-1259
kingmanlumber@yahoo.com

Claver same ticket

Mindy

*AEC-Claver #2
5092
OSW10481369*

INVOICE 177649
DATE : 06/22/09 12:42:23 PM
CLERK : Jones
PO :
SIGN :
CUSTOMER : Cash Sale

KINGMAN LUMBER CO
210 N SPRUCE
KINGMAN, KS 67068
620-532-3831
DATE: 06/22/09 TIME: 12:42
MER#: 6807620926201 TER#: 0001
S-A-L-E-S D-R-A-F-T

REF: 0005 BCH: 365
CD TYPE: MC
Q TYPE: PR
AMOUNT: \$36.35
ADCT: ~~XXXXXXXXXXXX4992~~ EXP: 12/09
PF 865348

Qty	Item	Desc	Unit Price	Extended
3	PORTLAND	PORTLAND CEMENT TYPE	\$11.40	\$34.20

Each			\$11.40	\$34.20
------	--	--	---------	---------

SUBTOTAL :	\$34.20
DISCOUNT :	\$0.00
SALESTAX :	\$2.15
SHIPPING :	\$0.00
TOTAL :	\$36.35
CREDIT CARD TENDERED :	\$36.35
CHANGE :	\$0.00

CARDMEMBER ACKNOWLEDGES RECEIPT OF
GOODS AND/OR SERVICES IN THE AMOUNT OF
THE TOTAL SHOWN HEREON AND AGREES TO
PERFORM THE OBLIGATIONS SET FORTH BY THE
CARDMEMBER'S AGREEMENT WITH THE ISSUER
[Signature]
TOP COPY-MERCHANT BOTTOM COPY-CUSTOMER

RECEIVED
JUN 10 2009
KCC WICHITA