

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 035-02088-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 11-9-1945

Well Operator: W. D. Short Oil Co., LLC KCC License #: 33608
(Owner / Company Name) (Operator's)
Address: P.O. Box 729 City: Oxford
State: Kansas Zip Code: 67119 Contact Phone: (620) 455 - 3576
Lease: Waldschmidt (Rahn Unit #1) Well #: 1 Sec. 6 Twp. 34S S. R. 6 East West
SW NE 22 - SW - SE Spot Location / QQQQ County: Cowley

1100 724 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)
1650 1695 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8-5/8" Set at: 81' Cemented with: Surface Sacks
Production Casing Size: 5-1/2" Set at: 2850' Cemented with: 100 Sacks

List (ALL) Perforations and Bridgeplug Sets: 2890-91

Elevation: 1116 (G.L. / K.B.) T.D.: 2875' PBTD: _____ Anhydrite Depth: unknown
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole
Proposed Method of Plugging (attach a separate page if additional space is needed): Per KCC Requirements

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No
If not explain why? Do not have drillers or electric log in file.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Mike Anstine
Phone: (620) 218 - 1822
Address: P.O. Box 729 City / State: Oxford, Kansas
Plugging Contractor: Kivett Plugging + Pipe Pulling Inc KCC License #: 34271
(Company Name) (Contractor's)
Address: P.O. Box 134, 402 N. 13th St., Blackwell, Ok. 74631 Phone: (620) 438 - 2856

Proposed Date and Hour of Plugging (if known?): Aug. 14, 2009

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: 7-27-2009 Authorized Operator / Agent: Will Short (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KANSAS CORPORATION COMMISSION
RECEIVED
JUL 29 2009

Dist 2
PAT

NEW WELL COMPLETION AND/OR ABANDONMENT RECORD

A. F. E. No. 6250

1 Dist. North Okla. Field Rahn Pool Lease B. I. Oxford Well No. 1
 2 Co. Cowley State Kansas Contractor Earl F. Wakofield T.D. 2875' P.D. - ft.
 3 Landing Flange Elev. - ft. Depth Measured From -; Height of Measuring Point from Landing Flange - ft.
 4 Date: Spudded 11-9-45 Drilling Completed 11-23-45 Tested - Rig Released -

CASING, LINER AND TUBING RECORD

SIZE O. D. IN.	WT. LB./FT.	THREADS NO. & TYPE	GRADE AND MAKE	NEW OR S. H.	E. L. L. W. SMLS.	DEPTH SET FT.	MEASUREMENTS INC. THREADS			TOP OF LINER	NO. OF JOINTS	HOLE SIZE
							QUANTITY SET	QUANTITY PULLED	QUANTITY LEFT IN HOLE			
8-5/8"						-	81'	None	81'			
5 1/2"						-	2850'	None	2850'			

CEMENTING RECORD

METHOD	MAKE AND TYPE CEMENT	SACKS USED	SQUEEZED AWAY	NO. OF BATCHES	FINAL PRESSURE	SLURRY WT. LB./GAL.	HOURS SET	DEPTH		REMARKS: TEMP. CALIPER, OTHER LOGS.
								FROM	TO	
No record										

ACIDIZATION AND SHOT RECORD

DATE	PRODUCTION OR P. I.		HOW TEST MADE	GAL. ACID	SHOT QTS.	DEPTH		NAME OF ZONE	TYPE FORMATION	REMARKS
	BEFORE	AFTER				FROM	TO			
No record										

SECTION PERFORATED

NAME OF PAY	DEPTH		SIZE OF HOLE	HOLES PER FOOT	DATE	SERVICE CO. OR TYPE SLOTS	REMARKS
	FROM	TO					
No record							

PRODUCING EQUIPMENT

29 RODS: Number No record in., Number _____ Size _____ in., Total Singles _____ Length _____ ft.
 30 PUMP: Size _____ Plunger Diam. _____ Make _____ Type _____
 31 PUMPING UNIT: Make _____ Type _____ Stroke _____ in. @ _____ RPM
 32 Torque @ 20 SPM _____ in. lbs.; Gear Box _____ H.P., Prime Mover Make _____
 33 H.P. @ _____ RPM. Other Remarks _____
 34 GAS ANCHOR _____
 35 OTHER LIFT EQUIPMENT _____

KANSAS CORPORATION COMMISSION

JUL 29 2009

RECEIVED {ALSO SEE SKETCH ON REVERSE SIDE}

PRODUCING STRATA

NAME	TOP	BASE	POROSITY %	PERM. md.	NET THICKNESS ft.	REMARKS: STATE CONTENTS OF ALL PRODUCING STRATA, O. G. & W., GIVING FLUID CONTACTS, D. S. T., ETC.
Bartlesville Sand	?	2875'				

REMARKS: This is one of the first producing wells in the Rahn Pool purchased by C. O. Co. which took over operations October 25th, 1948. Drilled with rotary tools from surface to 2862', Drilled from 2862' to a total depth of 2875' with cable tools. Producing formation Bartlesville sand. This well at the present time is producing 4 barrels of oil and 1/2 barrel of water in a 24 hour period.

(No other records available)

56 Estimate Total Cost \$ _____ Conoco Interest 100 % Operated by Continental Oil Company
 57 Potential _____ b/d-Mcf/d _____ @ _____ %TP and %CP on _____ Hr. Test Meas. Est. Allowable _____ b/d
 58 Other Production or Well Test Results _____

59 Signed _____ District Superintendent
 60 Signed _____ Division Superintendent
 61 Signed _____ Region Manager
 62 Signed _____ District Engineer
 63 Prepared by J. Bartrug Date 1-14-49
 64 DISTRIBUTED TO
 Mgr. P. & D. W.C.M. Acct'g E.H.L.
 Region L.P.C. District File
 Others _____

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg. Wichita, Kansas


COPY

Company W. D. MOORER ET AL
Farm Oxford No. 1

SEC. 6 T. 34 S. 6 E
CEL SW SE

Total Depth. 2887' ?
Comm. 11-9-45 Comp. 11-27-45
Shot or Treated.
Contractor Earl F. Wakarfield
issued. 2-23-48

County. Cowley
KANSAS



CASING:
8 5/8" 81'
5 1/2" 2878'

Elevation.....

Production. Est. 250 B.

Figures indicate Bottom of Formations.

clay	18
gravel	30
lime	130
red bed	167
lime & shale	410
sand	440
lime & shale	646
sand	678
lime & shale	730
shale	966
lime	1042
shale	1065
shale & lime	1158
sand	1265
lime	1320
lime & shale	1685
sand	1763
sand & shale	1778
lime & shale	1898
sand	1953
shale & shells	2055
shale sdy	2121
sand	2235
shale	2300
sand	2350
lime	2387
lime & shale	2830
shale sdy	2853
sand	2862
sand ?	2887 ?
Total Depth.	

KANSAS CORPORATION COMMISSION

JUL 29 2009
RECEIVED

6.2 ft/yr < 100 630'



CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

W.D. SHORT OIL CO., LLC
102 S RIVER RD
PO BOX 729
OXFORD, KS 67119-8801

July 31, 2009

Re: WALDSCHMIDT #1
API 15-035-02088-00-00
6-34S-6E, 724 FSL 1695 FEL
COWLEY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after January 27, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000