

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
March 2009
**This Form must be Typed
Form must be Signed
All blanks must be Filled**

OPERATOR: License #: 33608
Name: W. D. Short Oil Co. LLC
Address 1: P.O. Box 729
Address 2: 102 S. River Rd.
City: Oxford State: Ks Zip: 67119 + 0729
Contact Person: William D. (Don) Short Jr.
Phone: (620) 455-3576

API No. 15 - 035-22496-00-00
If pre 1967, supply original completion date: 4-12-1980
Spot Description: _____
NE NE SW Sec. 5 Twp. 34 S. R. 6 East West
2310 2318 Feet from North South Line of Section
2310 3150 Feet from East West Line of Section
Footages Calculated from Nearest Outside Corner:
 NE NW SE SW
County: Cowley
Lease Name: Waldschmidt Well #: A#5

Check One: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: _____
 SWD Permit #: _____ ENHR Permit #: _____ Gas Storage Permit #: _____
Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8-5/8" Set at: 212' Cemented with: 200sx Sacks
Production Casing Size: 5-1/2" Set at: 3039' Cemented with: 175sx Sacks

List (ALL) Perforations and Bridge Plug Sets:

Elevation: 1207 (G.L. / K.B.) T.D.: 3039' PBDT: _____ Anhydrite Depth: 700'
(Stone Corral Formation)

Condition of Well: Good Poor Junk in Hole Casing Leak at: _____
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

KANSAS CORPORATION COMMISSION

Per KCC Instructions

**JUL 29 2009
RECEIVED**

Is Well Log attached to this application? Yes No Is ACO-1 filed? Yes No

If ACO-1 not filed, explain why:

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Mike Anstine
Address: P.O. Box 729, 102 S. River Rd. City: Oxford State: Ks Zip: 67119 + 0729
Phone: (620) 218-1822
Plugging Contractor License #: 34271 Name: Kivett Plugging
Address 1: P.O. Box 134 Address 2: 402 N. 13th St.
City: Blackwell State: Ok Zip: 74631 + 0134
Phone: (580) 763-7748

Proposed Date of Plugging (if known): Aug. 14, 2009

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: July 27, 2009 Authorized Operator / Agent: [Signature] (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

DIST 2
PKT

This form shall be filed in duplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on side one will be of public record and side two will then be held confidential.

Circle one: Oil, Gas, Dry, SWD, OWWO, Injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, SWD and injection, T.A.

Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). KCC # (316) 263-3238. (Rules 82-2-105 & 82-2-125)

OPERATOR W. D. Short

API NO. 15-035-22496

ADDRESS Box 45

COUNTY Cowley

Oxford, Kansas

FIELD Rahn

**CONTACT PERSON W. D. Short

PROD. FORMATION Miss.

PHONE 316-455-3694

LEASE Waldschmidt

PURCHASER Total Pet. Co.

WELL NO. 5

ADDRESS Arkansas City, Kansas

WELL LOCATION NE NE SW

DRILLING White & Ellis

330 Ft. from West Line and

CONTRACTOR 1416 W. 6th

330 Ft. from North Line of

ADDRESS El Dorado, Kansas 67042

the 5 SEC. 34 TWP. 6 RGE. E

WELL PLAT

KCC _____
KCS _____
(Office Use)

PLUGGING CONTRACTOR ADDRESS

TOTAL DEPTH 3040 PBD

SPUD DATE 4-12-80 DATE COMPLETED 4-18-80

ELEV: GR 1202 DF KB

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS

Amount of surface pipe set and cemented 207 DV Tool Used?

AFFIDAVIT

STATE OF Kansas, COUNTY OF Cowley ss, I, W. D. Short

OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS operator (FOR)(OF)

OPERATOR OF THE Waldschmidt LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. _____ ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 7 DAY OF May, 19 80, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

SUBSCRIBED AND SWORN BEFORE ME THIS 5 DAY OF May, 19 80.

(s) W.D. Short

Margie O. Short
NOTARY PUBLIC

MY COMMISSION EXPIRES: Oct 11, 1984

**The person who can be reached by phone regarding any questions concerning this information. Within 45 days of completion, a witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

SIDE TWO

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Cellar	0	7	Kansas City	2433
Shale, Lime	7	1198		
Sand	1198	1313		
Lime, Shale, Sand	1313	1332		
Lime, Shale	1332	1360		
Shale	1360	1475		
Shale, Lime	1475	1704		
Shale, Sand	1704	1895		
Sand	1895	2000		
Shale	2000	2295		
Sand, Shale	2295	2340		
Shale	2340	2415		
Sand, Shale	2415	2433		
Lime	2433	2520		
Shale	2520	2605		
Lime	2605	2750		
Shale	2750	3040		

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lb./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	10 3/4	8 5/8	28#	207	Common	175	3% C.C.
Oil String	7 7/8	5 1/2	17#	3039	60-40 Pos. mix	200	none

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval
2	90 gram	2999-3007

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 gal. mud acid & 500# Sand	2999-3007

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
5-7-80	Pumping	

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	7 bbls.		90 MCF	100

Disposition of gas (vented, used on lease or sold)	Perforations
	2999-3007

KANSAS CORPORATION COMMISSION
 JUL 29 2009
 RECEIVED



CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

W.D. SHORT OIL CO., LLC
102 S RIVER RD
PO BOX 729
OXFORD, KS 67119-8801

July 31, 2009

Re: WALDSCHMIDT A #5
API 15-035-22496-00-00
5-34S-6E, 2318 FSL 3150 FEL
COWLEY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after January 27, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000