

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
March 2009  
**This Form must be Typed  
Form must be Signed  
All blanks must be Filled**

OPERATOR: License #: 33608  
Name: W. D. Short Oil Co. LLC  
Address 1: P.O. Box 729  
Address 2: 102 S. River Rd.  
City: Oxford State: Ks Zip: 67119 + 0729  
Contact Person: William D. (Don) Short Jr.  
Phone: ( 620 ) 455-3576

API No. 15 - 035-20830 - 0000  
If pre 1967, supply original completion date: 7-15-1975  
Spot Description: \_\_\_\_\_  
Sec. 5 Twp. 34 S. R. 6  East  West  
2,360 Feet from  North /  South Line of Section  
1,650 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Cowley  
Lease Name: COX Well #: 2-A

Check One:  Oil Well  Gas Well  OG  D&A  Cathodic  Water Supply Well  Other: \_\_\_\_\_  
 SWD Permit #: \_\_\_\_\_  ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks  
Surface Casing Size: 8-5/8" Set at: 155' Cemented with: 125sx Sacks  
Production Casing Size: 5-1/2" Set at: 2186" Cemented with: 150sx Sacks

List (ALL) Perforations and Bridge Plug Sets:  
**Perfs: 1940-43, 1943-53, 1960-96**

Elevation: 1198 (  G.L. /  K.B. ) T.D.: 2194 PBDT: \_\_\_\_\_ Anhydrite Depth: 439'  
(Stone Corral Formation)  
Condition of Well:  Good  Poor  Junk in Hole  Casing Leak at: \_\_\_\_\_  
(Interval)  
Proposed Method of Plugging (attach a separate page if additional space is needed):

**Per KCC Instructions**

Is Well Log attached to this application?  Yes  No Is ACO-1 filed?  Yes  No  
If ACO-1 not filed, explain why:

KANSAS CORPORATION COMMISSION  
**JUL 29 2009**  
**RECEIVED**

**Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission**

Company Representative authorized to supervise plugging operations: Mike Anstine  
Address: P.O. Box 729, 102 S. River Rd. City: Oxford State: Ks Zip: 67119 + 0729  
Phone: ( 620 ) 218-1822  
Plugging Contractor License #: 34271 Name: Kivett Plugging  
Address 1: P.O. Box 134 Address 2: 402 N. 13th St.  
City: Blackwell State: Ok Zip: 74631 + 0134  
Phone: ( 580 ) 763-7748

Proposed Date of Plugging (if known): Aug. 14, 2009

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: July 27, 2009 Authorized Operator / Agent: Will Anstine (Signature)

*Dist 2  
PCT*

PAUL D. KOONTZ  
 GEOLOGIST  
 1954 BELMONT  
 EL DORADO, KANSAS 67042

July 19, 1975

MR. W. D. SHORT  
 P. O. Box 45  
 Oxford, Kansas 67119

Re: Cox 2-A, SW-SE-NW  
 Section 5-34S-6E  
 Cowley County, Kansas

Dear Sir:

This report on the subject well is based on microscopic examination of rotary cuttings from 1400' to the total depth of 2194'. All measurements were taken from the rotary drive bushing, which was 3' above derrick floor and 5' above ground level.

The following tops were picked:

Elevation RB	(+1198)
Toronto Limestone	1456 (- 258)
Douglas Shale	1473 (- 275)
Douglas Sand	1506 (- 308)
Brown Lime	1693 (- 495)
Stalnaker Sand	1721 (- 523)
Parry Sand	1938 (- 740)
Iola Limestone	2165 (- 967)
Layton Sand	2125 (- 927)
R.T.L.	2195 (- 996)
Casing Point	2186 (- 988)

Shows of oil are as follows:

STALNAKER SAND

1721-43'. Sand, grey, angular, micaceous, platy, with slight porosity, and no odor, staining or fluorescence. Does not merit testing.

1755-70'. Sand, grey to brown, medium, angular, micaceous. Good to fair granular porosity, with light spotted staining and free oil. Fair odor, and spotted, rich to light fluorescence. Zone probably carries water, but merits testing before well is abandoned.

KANSAS CORPORATION COMMISSION

JUL 29 2009

RECEIVED

PAUL D. KOONTZ  
GEOLOGIST  
1954 BELMONT  
EL DORADO, KANSAS 67042

July 19, 1975

MR. W. D. SHORT  
Cox 2-A, SW-SE-NW  
Section 5-34S-6E  
Cowley County, Kansas

Page 2

PARRY SAND


1938-58'. Sand, grey, angular, micaceous, medium grain, with good to fair granular porosity and strong odor, rich fluorescence and shows of free gassy oil. Zone appears to carry commercial oil, but should be tested in top 10', to lessen water problems.

LAYTON SAND

2185-94'. Sand, grey, angular, medium, with fair granular porosity, good odor. Light even staining and rich fluorescence. Zone should produce commercial oil.

It was recommended that 5½ be set and cemented @2186' (8' off bottom) to test the Stalnaker, Parry, and Layton Sands.

Thank You



PAUL D. KOONTZ  
Geologist

KANSAS CORPORATION COMMISSION

JUL 29 2009  
RECEIVED



CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

W.D. SHORT OIL CO., LLC  
102 S RIVER RD  
PO BOX 729  
OXFORD, KS 67119-8801

August 03, 2009

Re: COX #2-A  
API 15-035-20830-00-00  
5-34S-6E, 2360 FNL 1650 FWL  
COWLEY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after January 30, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,

Steve Bond  
Production Department Supervisor

District: #2  
3450 N. Rock Road, Suite 601  
Wichita, KS 67226  
(316) 630-4000