

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Oxy USA, Inc
Address: PO Box 2528 Liberal KS 67905
Phone: 620/629 4200 Operator License #: 5447
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 6-18-09 (Date)
by: Eric MacLaren (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Chester Depth to Top: 6498' Bottom: 6526' T.D. 6829'

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-189-20656-0002
Lease Name: Kinney Chester Sand Unit
Well Number: 701 W KCCPKR
Spot Location (QQQQ): W2 E/2 - SE - NE
1980 Feet from North / South Section Line
510 Feet from East / West Section Line
Sec. 35 Twp. 34 S. R. 35 East West
County: Stevens
Date Well Completed: 5-27-83 Spud
Plugging Commenced: 6-22-09
Plugging Completed: 6-22-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				20	20	-
				8 5/8	1660	-
				5 1/2	6829	2801

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

2 3/8 was stuck below 3100. Pumped 50 sx @ perfs 6498 to 6098 est.
Cut 2 3/8 @ 3101. 25 sx plug @ stub from 3101 to 2901
Shot & pull 5 1/2 to 1680. Circ. hole w/mud & mixed 50 sx plug 1680 to 1530
40 sx 600 to 480 10sx 40 to 0 Capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151
Address: RT. 1, Box 49 BA Tyrone, OK 73951-9731
Name of Party Responsible for Plugging Fees: Oxy USA Inc, 1701 N Kansas, PO Box 2528, Liberal, KS, 67905
State of Kansas County, Seward, ss.

Kenny Andrews (Employee of Operator) or (Operator) on above described well being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above described well is as filed, and the same are true and correct, so help me God.

RECEIVED
JUL 22 2009

KCC WICHITA

ANITA PETERSON
Notary Public - State of Kansas
My Appt. Expires October 1, 2009

(Signature) [Signature]
(Address) PO Box 2528 Liberal, ks.
SUBSCRIBED and SWORN TO before me this 20 day of July, 2009
Anita Peterson My Commission Expires: Oct 1, 2009
Notary Public

[Handwritten initials]