

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 5893  
Name: Pratt Well Service, Inc.  
Address 1: PO Box 907  
Address 2: \_\_\_\_\_  
City: Pratt State: KS Zip: 67124 + \_\_\_\_\_  
Contact Person: Kenneth C. Gates  
Phone: (620) 672-9571 Ext 5  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: E-28889  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
Mississippi Depth to Top: 5148 Bottom: 5202 T.D. 5265  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 033-20796-00-01  
Spot Description: \_\_\_\_\_  
NW NW SW Sec. 17 Twp. 31 S. R. 18  East  West  
2,217 Feet from  North /  South Line of Section  
4,953 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Comanche  
Lease Name: Burkhall Well #: 1  
Date Well Completed: 12/28/1990  
The plugging proposal was approved on: 7/23/2009 (Date)  
by: Steve Bond (KCC District Agent's Name)  
Plugging Commenced: 07/24/2009  
Plugging Completed: 07/27/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	663'	
		Production	5 1/2"	5252'	2100'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP at 4950' with 2 sacks cement. Cut casing at 2100'. Set 1st plug at 1167' 12 sacks gel and 50 sacks 60-40 poz. 2nd plug at 690' with 50 sacks cement. 3rd plug at 340' with 30 sacks cement. 4th plug at 40' 20 sacks, cement to surface.

Plugging Contractor License #: 5893 Name: Pratt Well Service, Inc.  
Address 1: PO Box 907 Address 2: \_\_\_\_\_  
City: Pratt State: KS Zip: 67124 + \_\_\_\_\_  
Phone: (620) 672-9571 ext 9  
Name of Party Responsible for Plugging Fees: Pratt Well Service, Inc.  
State of Kansas County, Pratt, ss.  
Kenneth C. Gates  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.  
Signature: Kenneth C. Gates 7/28/09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KANSAS CORPORATION COMMISSION

JUL 30 2009

RECEIVED



# LOG-TECH OF KANSAS, INC.

86 SW 10 AVE.

GREAT BEND, KANSAS 67530

(620) 792-2167

INVOICE

**5791**

Date 7-24-2009

CHARGE TO: Platt Well Service  
 ADDRESS \_\_\_\_\_  
 R/A SOURCE NO. \_\_\_\_\_ CUSTOMER ORDER NO. \_\_\_\_\_  
 LEASE AND WELL NO. Duck Hill #1 FIELD \_\_\_\_\_  
 NEAREST TOWN Coldwater COUNTY Canadian STATE K.S.  
 SPOT LOCATION NW-NW-SW SEC. 17 TWP. 7N RANGE 18W  
 ZERO 5' ALL CASING SIZE 5 1/2 WEIGHT \_\_\_\_\_  
 CUSTOMER'S T.D. \_\_\_\_\_ LOG TECH \_\_\_\_\_ FLUID LEVEL \_\_\_\_\_  
 ENGINEER Lance Gregg OPERATOR C. Chandler, J. Frisberger

PERFORATING				
Description	No. Shots	From Depth	To	Amount
<u>PVC Bump cut casing</u>	<u>1</u>	<u>2100</u>	<u>2101</u>	<u>850.00</u>

DEPTH AND OPERATIONS CHARGES					
Description	From Depth	To	Total No. Ft.	Price Per Ft.	Amount
<u>Set 5 1/2 CIBP A+</u>	<u>0</u>	<u>4950</u>	<u>4950</u>	<u>.22</u>	<u>1089.00</u>
<u>Deep cement A+</u>	<u>0</u>	<u>4950</u>	<u>4950</u>	<u>.036</u>	<u>180.00</u>

MISCELLANEOUS		
Description	Quantity	Amount
<u>Service Charge</u>	<u>1</u>	<u>550.00</u>
<u>5 1/2 CIBP Dis-S weather seal plug</u>	<u>1</u>	<u>700.00</u>

PRICES SUBJECT TO CORRECTION BY BILLING DEPARTMENT

RECEIVED THE ABOVE SERVICES ACCORDING TO THE TERMS AND CONDITIONS SPECIFIED ON THE REVERSE SIDE TO WHICH WE HEREBY AGREE.

[Signature]  
 Customer Signature \_\_\_\_\_ Date \_\_\_\_\_

Code Ref. ....	Sub Total	<u>3369.00</u>
.....	Tax/Insurance	
.....	Tax	
<u>Discount</u>		<u>2695.00</u>