

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 9860
Name: Castle Resources Inc.
Address 1: PO Box 87
Address 2: _____
City: Schoenchen State: KS Zip: 67667 + _____
Contact Person: Jerry Green
Phone: (785) 625-5155
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Miss Depth to Top: 5044 Bottom: 5156 T.D. 5261
Morrow SS Depth to Top: 4994 Bottom: 5014 T.D. 5261
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 055-21580 - 0000
Spot Description: _____
NW NW NW _____ Sec. 18 Twp. 26 S. R. 33 East West
330 Feet from North / South Line of Section
330 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Finney
Lease Name: Stone A Well #: 1
Date Well Completed: _____
The plugging proposal was approved on: _____ (Date)
by: _____ (KCC District Agent's Name)
Plugging Commenced: 4-30-09
Plugging Completed: 4-30-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Miss 5138-44	exhausted	surface	8 5/8	1892	0
Morrow SS 4944-5010	exhausted	long string	4 1/2	5254	1750'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

125 sacks and 100# of hulls at 1750'. Followed by 20 sacks of gel and 50 sacks of 60/40 poz with 100# of hulls. Displace 22BBI H2O pull to 90' mix 40 sacks, displace 10BBI pull to 40' top off with 20 sacks.

KCC PKT PH
CP 2/3

Geist, Ron DBA Wildcat Well Service

KANSAS CORPORATION COMMISSION

JUL 31 2009
RECEIVED

Plugging Contractor License #: 33612 Name: Allied Cementing Co., Inc.
Address 1: PO Box 31 Address 2: _____
City: Russell State: KS Zip: 67665 + _____
Phone: (785) 483-2627
Name of Party Responsible for Plugging Fees: Castle Resources Inc.
State of Kansas County, Ellis, ss.
Jerry Green Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: _____
Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT